

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Clare</u> (County)		Located In:	Corner Code #
1. Public Land Survey		T 17N R 5W	L9
		T R	
2. Property Controlling in Section	S	T R	
	S	T R	
3. Miscellaneous Property in Sec.	S	T R	
	S	T R	

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on July 28, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L9 - 1837, GLO, set quarter section post, H. Nicholson.
 Hemlock 10" N 35° E 4 Links
 Hemlock 6" S 20° E 8 Links
- County Survey Record, Book 6, p. 25.
 Pine stump 24" N 44.5° E 23 Links
 Fence post 8" N 6.5° W 53 Links
- 1977, P. Lapham, LCRC #306-77, found a 1" square bar.
 Power pole S 45° W 40.30'
 10" Cherry N 05° E 32.40'
 6" White Pine N 35° E 66.85'



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L9 - 1/4 corner common to Sec. 24 & 25 - Found a 1" square iron bar - 1' deep in Maple Grove Rd. - CL of gravel is 3.5' N. 1" iron bar accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L9 - 1" square bar
 N5°E 32.54' to set nail and tag in E side 14" Cherry (PBL)
 North 32.90' to Fd. capped iron rod #9433
 S55°W 40.28' to nail in SE side Power Pole (PBL)
 N64°E 74.75' to set nail and tag in W side 12" White Pine

Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 10/18/2000