

FEB 18 1994

**CLARE COUNTY REMONUMENTATION PROGRAM**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED  
 E 11 A  
 1993 DEC 20 PM 1:44  
 REGISTER OF DEEDS  
 CLARE COUNTY  
 DONNA M. CARR

For corners in

<u>CLARE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>6W</u>	<u>C-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7		•											
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARK R. ROBISON, in a field survey on OCTOBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 1847 ORSON LYON, POST, W. PINE S 17°E, 26 LKS P.341  
 NORWAY PINE N 23-1/4°W, 64 LKS  
 11-6-73 LAPHAM, LCRC 119-73

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 FOUND 10" DIA. CONC. & STONE MONUMENT WITH INVERTED WELL POINT IN CENTER. WELL POINT WAS RUSTED OFF ABOUT 1.5' BELOW SURFACE OF ROAD. MONUMENT HAD BEEN RAISED WITH 12" x 5/8" DIA. SUCKER ROD. PLACED 5/8" DIA. x 8" COUNTY SURVEY MONUMENT RE-BAR OVER WELL POINT & REPLACED OLD STONES IN FRESH CONCRETE. LEFT WELL POINT & SUCKER ROD IN CONC. MONUMENT.  
 FOUND RECORDED WITNESSES:  
 N 20°E, 34.26' - 10" OAK  
 N 60°E, 68.36' - 12" OAK  
 S 40°W, 58.35' - POWER POLE

This Corner established in Clare County Remonumentation Program.  
 See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 SET 5/8" X 8" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN OLD STONE & CONCRETE MONUMENT.  
 N 20°E, 34.31' - 20" OAK TREE  
 N 60°E, 68.35' - 21" OAK TREE  
 S 80°E, 179.11' - POWER POLE  
 S 40°W, 56.37' - POWER POLE



Signed by Mark R. Robison Date 11/30/93  
 Surveyor's Michigan License No. 27458