

**SURVEY &  
REMONUMENTATION**

FEB 18 1994

COMMISSION

**CLARE COUNTY REMONUMENTATION PROGRAM**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED  
E 11 A  
1993 DEC 20 PM 1:44  
REGISTER OF DEEDS  
CLARE COUNTY  
DONNA M. CARR

For corners in

<u>CLARE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>6W</u>	<u>D-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, MARK R. ROBISON, in a field survey on OCTOBER, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
 1847 ORSON LYON, POST, P.342  
 6-16-08 A. JOHNSON, CSR 4-142  
 11-06-73 LAPHAM, LCRC 119-73  
 12-07-76 McCLUNG, LCRC 453-84  
 12-03-76 McCLUNG, LCRC 449-84

LCRC 449-84 APPEARS TO REFERENCE CORNER D-7 INCORRECTLY.  
 THESE WITNESSES (FOR D-7) ARE THE SAME WITNESSES RECORDED IN LCRC 453-84 FOR CORNER E-7.  
 THESE WITNESSES ALSO FIT CORNER E-7 ON THE GROUND

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 FOUND CAPPED IRON IN STEEL FENCE POST IN WOOD STAKE. DUG OUT 18" RE-ROD. LEFT "U" SHAPED FENCE POST AND WOOD STAKE. SET 5/8" x 36" ROD IN STEEL FENCE POST IN PLACE OF FOUND CAPPED IRON.  
 FOUND RECORDED WITNESSES:  
 N 55°W, 69.59' - 15" OAK, BLAZED  
 N 25°E, 95.66' - 10" PINE, BLAZED  
 S 75°W, 119.66' (MEAS. 123±) - 24" OAK, UNBLAZED (MAY NOT BE O.B.T.)

This Corner established in Clare County Remonumentation Program.  
 See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP.  
 N 25°E, 95.66' - 15" NORWAY PINE  
 N 55°W, 69.93' - 22" OAK  
 S 75°W, 122.95' - 24" OAK  
 S 35°E, 61.58' - POWER POLE



Signed by Mark Robison Date 11/30/93

Surveyor's Michigan License No. 27458