

**SURVEY &
REMONUMENTATION**

JAN 23 2001

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

Clare County Remonumentation

For Corners in
Clare

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 17N R. 6W D-13
- T. _____ R. _____
- T. _____ R. _____
- 2. Public Controlling S. _____ T. _____ R. _____
- in Section S. _____ T. _____ R. _____
- 3. Miscellaneous S. _____ T. _____ R. _____
- Property in Section S. _____ T. _____ R. _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

200000010149
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 12-15-2000 At 07:44 am.
LAND CORNER 9.00
OR Liber 2 Page 272 - 272

Instrument Liber Page
200000010149 OR 2 272

477-00

Register of Deeds Stamp & File Number

I, Jan S. Fokens, in a field survey on March 6, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1. G.L.O Original Survey:
Township: 2nd Quarter 1837 John Hodgson
Pages 299 original field notes
- 2. County Survey Records:
None of Record
- 3. L.C.R.C.:
Liber 467, Page 85 Paul B. Lapham 1984 Set 1/2" capped re-rod single proportion measurement
Liber 887, Page 99 Mark Robison 1999 Found 1/2" capped re-rod
- 4. Surveys of Record:
None of Record
- 5. Unrecorded Survey:

Paul B. Lapham survey 1984 Found 1/2" capped re-rod
Paul B. Lapham survey 1988 Found 1/2" capped re-rod
Paul B. Lapham survey 1999 Found 1/2" capped re-rod

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman *Paul B. Lapham*
Date 9-13-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Existent corner established in Clare County Remonumentation Program. See dossier for detailed report.

- 1. Found capped iron, cap unreadable
- 2. Found wood pieces laying down to the south of iron. Wood was at many different angles
- 3. Excavated to 2.5'. Original soil at 1.0'. No further evidence.

Accepted as the best available evidence of the position of the original corner and replaced with Standard Monument Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set Standard Clare County Monument in Monument Box, stamped D-13/17-6 and D-1/16-6 and PS 21567.

- D-13 S. 1/4 Corner, Section 32, T.17N.-R.6W., Garfield Township, Clare Co., MI.**
- S.68°W. 57.76' Set nail and tag in North face of 4" wood fence post
 - N.15°E. 64.65' Set nail and tag in West face of new power pole
 - S.57°E. 35.89' Top center of large boulder
 - East. 52.67' Found capped iron, property controlling corner
 - S.89°38'31"E 2646.12' E-13 Corner common sections 32 & 33, T.17N.-R.6W., Garfield Twp., Clare Co., MI.
 - N.89°38'11"W. 2645.94' C-13 Corner common to sections 31 & 32, T.17N.-R.6W., Garfield Twp., Clare Co., MI.

Signed by

Surveyor's Michigan License No. 21567

Date

12/12/00

