

**SURVEY & REMONUMENTATION**

**CLARE COUNTY REMONUMENTATION PROGRAM**

FEB 18 1994

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED  
 E 1 A  
 1993 DEC 20 PM 1:45  
 REGISTER OF DEEDS  
 CLARE COUNTY  
 DONNA M. CARR

For corners in COMMISSION

<u>CLARE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>6W</u>	<u>E-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARK R. ROBISON, in a field survey on OCTOBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
 1847 ORSON LYON, POST, BEECH 14" S 81-3/4°W, 15 LKS P.332  
 ASPEN 12" N 54-1/2°E, 7 LKS  
 NO DATE, UNIDENTIFIED, W. PINE 36" N 44°W, 63 LKS CSR 6-174  
 W. PINE 28" S 34°W, 58 LKS  
 4-19-71 LAPHAM, LCRC 2-71  
 6-11-91 McLANE, LCRC 612-91

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 FOUND CAPPED IRON IN ASPHALT PAVEMENT  
 FOUND RECORDED WITNESSES:  
 N 40°E, 82.71' - 12" RED PINE  
 S 45°W, 99.5' - POWER POLE

This Corner established in Clare County Remonumentation Program.  
 See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 SET 5/8" x 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MONUMENT BOX.  
 S 45°W, 99.50' - POWER POLE  
 N 65°E, 82.26' - 20" NORWAY PINE  
 N 20°W, 29.65' - COR. POST (10' HIGH)  
 N 50°W, 58.45' - 4th POST (10' HIGH)



Signed by Mark R. Robison

Date 11/24/93

Surveyor's Michigan License No. 27458