

SURVEY & REMONUMENTATION

FEB 18 1994

CLARE COUNTY REMONUMENTATION PROGRAM

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED
1993 DEC 20 PM 1:44
REGISTER OF DEEDS
CLARE COUNTY
DONNA M. CARR

For corners in

<u>CLARE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>6W</u>	<u>F-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, MARK R. ROBISON, in a field survey on OCTOBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1847 ORSON LYON, POST, HEMLOCK 16" N 62°E, 3 LKS P.334
 HEMLOCK 24" S 7-1/4°E, 65 LKS
 6-20-08 A. JOHNSON, W. PINE 28" N 3°W, 30 LKS CSR 4-140
 6-20-08 A. JOHNSON, W. PINE 28" N 3°W, 30 LKS CSR 6-166
 10-17-76 WHITTIER, LCRC 217-75
 12-03-76 McCLUNG, LCRC 449-84

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 1" PIPE RUSTED BUT IN EXCELLENT SHAPE.
 FOUND WITNESSES FOR LCRC 217-75, DID NOT FIND ANY WITNESSES FOR LCRC 449-84. (THESE MAY BE RECORDED IN ERROR). MET WITH McCLUNG, HIS DISTANCE FROM THIS CORNER FO THE S.W. CORNER OF SECTION 16 IN 2637.28', WE MEASURED 2637.30', THIS VERIFIES THE CORNER. LEFT 1" x 36"(+) PIPE.

This Corner established in Clare County Remonumentation Program.
See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 FOUND 1" x 36"(+) PIPE
 S 10°E, 37.60' - POWER POLE
 S 50°E, 42.07' - 20" NORWAY PINE
 NORTH, 73.88' - 24" OAK
 N 45°E, 64.97' - 15" OAK (CENTER OF TRIPLE OAK)



Signed by Mark R. Robison

Date 11/24/93

Surveyor's Michigan License No. 27458