

**SURVEY &
REMONUMENTATION**

JAN 23 2001

LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

Clare County Remonumentation

For Corners in
Clare

(County)

Located In:

Corner Code#:

1. Public Land Survey T. 17N R. 6W H-13
 T. _____ R. _____
 T. _____ R. _____
 2. Public Controlling S. _____ T. _____ R. _____
 in Section S. _____ T. _____ R. _____
 3. Miscellaneous S. _____ T. _____ R. _____
 Property in Section S. _____ T. _____ R. _____
 4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

200000010153
 Filed for Record in
 CLARE COUNTY MICHIGAN
 CAROL MCAULAY
 On 12-15-2000 At 07:44 am.
 LAND CORNER 9.00
 OR Liber 2 Page 276 - 276

Instrument Liber Page
 200000010153 OR 2 276

#481-00

Register of Deeds Stamp & File Number

I, Jan S. Fokens, in a field survey on March 6, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration: -

- G.L.O Original Survey:
Township: 2nd Quarter 1837 John Hodgson
Pages 298 original field notes
- County Survey Records:
None of Record
- L.C.R.C.:
None of Record
- Surveys of Record:
Liber 005, Page 369 John McLane October 31, 1994 Set 5/8" re-rod with cap & base of large painted post & 29' North of fence intersection.
- Unrecorded Survey:
Paul B. Lapham & Assoc. field notes Overall distances noted between G-1 and I-13/I-1

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman *[Signature]*
 Date 10-18-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Established corner in Clare County Remonumentation Program. See dossier for detailed report.

- Found capped iron #21273 at base of large painted post
- Did not excavate. Corner in water.

Accepted as the best available evidence of the position of the original corner and replaced with Standard Monument Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set Standard Clare County Monument in Monument Box, stamped H-13/17-6 and H-1/16-6 and PS 21567.

H-13 S. 1/4 Corner, Section 34, T.17N.-R.6W., Garfield Township, Clare Co., MI.

- | | | |
|---------------|----------|---|
| N.47°E. | 15.93' | Found nail And tag in south east face of 12" Elm with blazng. |
| N.11°E. | 20.32' | Found nail and tag in east face of 8" Elm with fence markings. |
| S.55°E. | 19.68' | Found nail and tag in south west face of 12" triple Maple. |
| S.52°W. | 28.99' | Found nail and tag in east face of 14" Birch |
| S.89°25'07"W. | 2648.96' | G-13 Corner common to sections 33 & 34, T.17N.-R.6W., Garfield Twp., Clare Co., MI. |
| N.89°34'36"E. | 2653.37' | I-13 Corner common to sections 34 & 35, T.17N.-R.6W., Garfield Twp., Clare Co., MI. |

Signed by *[Signature]*
 Surveyor's Michigan License No. 0003967



Date 10/12/00