

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CLARE Located In: Corner Code #
(County)

1. Public Land Survey T 17 N R 6 W J-7
T ___ R ___
T ___ R ___
T ___ R ___

2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___

3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

RECEIVED
E 11 11
153-96
96 NOV 14 PM 4:15
REGISTER OF DEEDS
CLARE COUNTY
DONNA M. CARR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on AUGUST, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

1847 LYON
WIT.-BEECH 14" N49°E 20 LKS.
BEECH 16" S21 3/4°W 37 LKS.

MSHD
INDICATES APPROXIMATE N-S 1/4 LINE AT STA. 791 & 85.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SET ON SINGLE PROPORTIONATE MEASURE BETWEEN I-7 AND K-7. CORNER FALLS APPROXIMATELY THREE FEET WEST OF NORTH & SOUTH FENCES AND 15.47 FEET NORTH OF CONSTRUCTION CENTERLINE OF U.S. 10.

See dossier for detailed report.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" x 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP.
ACCEPTED AS A FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE CORNER.

WITNESSES:
S04°E, 72.72' - N.E. CORNER OF 2 1/2' SQUARE STONE POST.
NORTH, 140.04' - NAIL & TAG IN CORNER FENCE POST.
N55°W, 143.76' - NAIL & TAG IN 24" R. OAK.
N73°E, 181.38' - NAIL & TAG IN POWER POLE.

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County
Chairman Donald H. Lytle
Date 11-07-96

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458



Date 9-23-96