

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Clare (County)	Located In	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>6W</u>	<u>H6</u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on June 1, 1999 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		19		20		21		
7													
8	15		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- H6
- CSR Bk. 2, P. 138- A.D. Johnson-1944-Survey SW 1/4 Sec. 15
 - 1976- LCRC # 237-76- P. Lapham- Fnd. 1/2" rod. N10°E 143.08' to 8" Cherry, South 63.47' to 6" Post, West 66.97' to 6" Post.
 - Un. Rec. Survey-Lapham & Assoc. #760948-1976 Fd. 1/2" rod- J. Meyers
 - Rec. Sur. L. 2, P. 387- 1978-P. Lapham- Fnd. 1/2" rod w/ record witnesses
 - Rec. Sur. L.3, P. 333- 1992-J. McLang- Fnd. 1/2" rod w / record witnesses

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

H6- C 1/4 corner of section 15- Didn't find 1/2" rod of record. Set 2" Aluminum Cap on 5/8" X 34" rebar at Meyer's distance east of the NE corner of 'Oman's Garfield Acres' on line extended east from G6. 2" AC falls on east edge of rotted off cedar fence post encased in concrete of fences N, S & W. Fd. rec. Wit. at N10°E 143' to 8" Cherry stump & West 67' to 6" Post (fallen over). 2" AC is leaning Easterly. 2" AC appears to represent position established in Johnson's 1944 survey and is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H6- 5/8" X 34" rebar with 2" Aluminum cap.
 S68°W 33.96' to set nail and tag in N. Side of 7" Cedar
 N30°W 29.45' to set 1/2" X 24" rebar
 S45°E 96.24' to set nail and tag in SW Side of 2" Pine
 Set Orange Carsonite 1' E.



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 10/18/2000