

**SURVEY &
REMONUMENTATION**

JAN 23, 2001

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation**

SECTION

For Corners in
Clare

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 17N R. 3W C-4
T. _____ R. _____
T. _____ R. _____
- 2. Public Controlling S. _____ T. _____ R. _____
in Section S. _____ T. _____ R. _____
- 3. Miscellaneous S. _____ T. _____ R. _____
Property in Section S. _____ T. _____ R. _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

200000009706
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 11-29-2000 At 10:31 am.
LAND CORNER 9.00
OR Liber 2 Page 236 - 236

Instrument Liber Page
200000009706 OR 2 236

441-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 16, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.
Nicholson, 1837

C.S.R.
Concross, 1886
Bk. 5 Pgs. 7 & 8
C-4 to C-3 = 39.72 C-4 to C-3 39.57
C-4 to C-5 = 39.90, 39.96

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman *Paul S. Leph*
Date 5-10-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 5/8" Sucker Rod on fence to East & West excavated 2 1/2 feet.
Found nothing further
Measure C-4 to C-3 = 2623.94
Measure C-4 to C-5 = 2652.22
Measure C-4 North to Fence line West 1310'
Measure C-4 South to Fence line West 1323'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 5/8" x 36" re-rod with Clare County Remon Cap marked P.S. #27458 in Mon. Box. Accepted found iron as best available evidence of accepted position of the corner.

Witnesses:
N25°E, 91.25' - N & T 15" Elm
N25°W, 94.58' - N & T 18" x 18" Elm
West, 29.55' - Telephone Riser
East, 33.65' - N & T Corner Fence Post



Signed by *Mark R. Robison*
Surveyor's Michigan License No. 27458

Date 5-28-2000