

**SURVEY &  
REMONUMENTATION**

**JAN 23 2001**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Clare County Remonumentation**

For Corners in  
Clare

(County)

Located In:

Corner Code#:

- |   |                            |            |
|---|----------------------------|------------|
| 1. Public Land Survey                   | T. <u>17N</u> R. <u>3W</u> | <u>C-7</u> |
|   | T. _____ R. _____          | _____      |
|   | T. _____ R. _____          | _____      |
| 2. Public Controlling<br>in Section     | S. _____ T. _____ R. _____ | _____      |
|   | S. _____ T. _____ R. _____ | _____      |
| 3. Miscellaneous<br>Property in Section | S. _____ T. _____ R. _____ | _____      |
|   | S. _____ T. _____ R. _____ | _____      |
| 4. Lot No. _____, Recorded Plat _____   |                            |            |
| 5. Private Claims _____                 |                            |            |

20000009291  
Filed for Record in  
CLARE COUNTY MICHIGAN  
CAROL MCAULAY  
On 11-14-2000 At 11:04 am.  
LAND CORNER 9.00  
OR Liber 2 Page 217 - 217

Instrument Liber Page  
20000009291 OR 2 217

#472-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 13, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Nicholson, 1837	C.S.R. Bk. 5, Pg. 20 Pine Stump 20"	
Re-Survey Burt, 1850	S64°W, 39 LINKS	Surveys Lapham, 1978 L2, Pg. 371
Found old corner and witness from 1837	LCRC Lapham, 1977 #264-77 Robison, 1999 #882-99	

**APPROVED LAND CORNER**  
**P.A. 345 of 1990**  
**Clare County**

Chairman Paul B. Lapham  
Date 5-20-00


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

Found 3/4" x 10" iron bar surrounded by stone. Excavated to 1' found nothing further.  
1 witness from #264-77 in poor condition  
4 witnesses from #882-99  
Measure C-7 to B-7 2650.76'  
D-7 to C-7 2637.04

Accepted found bar as best available evidence of accepted position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" re-rod with Clare County Remon Cap marked P.S. #27458.  
Witnesses:  
N73°E, 64.40' - N & T Ash Clump (OBT)  
S35°E, 40.88' - N & T Corner Fence Post (OBT)  
N75°W, 160.10' - Southwest corner fence around utility pole (OBT)  
N50°W, 49.78' - Corner Fence Post (OBT)



Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 11-13-2000