

CLARE COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
E D I M A
#184-96
96 DEC 23 AM 11:59
REGISTER OF DEEDS
CLARE COUNTY
DONNA M. CARR

For corners in

<u>CLARE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>3W</u>	<u>D - 5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on November, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	I
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1850 BURT SET 1/4 SEC POST WIT.-HEMLOCK 30 S72W 26 HEMLOCK 10 N70E 25	1993 WILCOX-CO ROAD PLANS FOUND P.K. NAIL W/ WASHER WIT.-N06E 32.47 COR FENCE POST N35W 38.68 6" ELM SOUTH 51.84 TW. 4" ASH S33E 60.97 CLUMP 4" ASH MEAS 2647.01 EAST TO E-5 MEAS 2548.90 WEST TO C-5
NO DATE (C.S.R. BK. 5 PG. 8) D-5 TO C-5 39.99 D-5 TO D-4 39.86	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND MON BOX BUT NO IRON. WITNESSES IN FENCE TO NORTH & 10" ELM TO N.W. INTERSECT OUTSIDE N.W RIM OF MON BOX. MEAS. 2647.1 EAST TO E-5. MEAS 2646.98 WEST TO C-5.

APPROVED LAND CORNER
P.A. 345 of 1980
Clare County

Chairman Paul G. [Signature]

Date 11-14-96

SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5: 1/4 CORNER COMMON TO SECTIONS 8 & 17
SET 5/8" X 36" REROD WITH 3" CLARE COUNTY MONUMENT CAP & MOVED MON BOX TO WITNESSED LOCATION. ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

WITNESSES:
N06E 32.47 N&T IN COR F. POST (OBT)
N25W 38.68 N&T IN 8" ASH (OBT CALLED ELM)
S70W 108.28 N&T IN 6" ELM
S78E 169.56 N&T IN 30" MAPLE



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 12-20-96