

**SURVEY &
REMONUMENTATION**

JAN 23 2001

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in
Clare
(County)

Located In: Corner Code#:

1. Public Land Survey T. 17N R. 3W E-7
T. _____ R. _____
T. _____ R. _____

2. Public Controlling S. _____ T. _____ R. _____
in Section S. _____ T. _____ R. _____

3. Miscellaneous S. _____ T. _____ R. _____
Property in Section S. _____ T. _____ R. _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

200000009292
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 11-14-2000 At 11:04 am.
LAND CORNER 9.00
OR Liber 2 Page 218 - 218

Instrument Liber Page
200000009292 OR 2 218

#423-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 14, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Burt, 1850
Elm 10" N25°E, 15 LINKS
Elm 6" S45°W, 15 LINKS

LCRC
Lapham #116-73
Found 1/2" Iron

C.S.R.,
Johnson, 1903, Bk. 1 Pg. 16
Iron stake 1 1/4" x 20" Center of Road
E-7 to F-7 39.79 (2626.14)

Surveys
Lapham L1. Pg. 538

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County
Chairman Paul H. Lapham
Date 5-10-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1 1/4" x 18" Pipe in
Centerline E-W Road 2' West of Centerline
North-South Road.

Measure E-7 to F-7, 2628.12

Witness from LCRC, #116-73
S45°E, 54.4 P.P.

Excavated 1' (+-) Found nothing more. Accepted found pipe as best available evidence of accepted position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" re-rod with Clare County Remon Cap marked P.S #27458.
Witnesses:
S45°E, 54.4' - N & T Southwest side P. Pole (OBT)
N77°W, 99.08' - N & T Southwest side of 6th Fence Post West from Corner
N42°W, 42.04' - Phone Riser
N15°E, 216.72' - West side of P.P.



Signed by Mark R. Robison Date 11-13-2000
Surveyor's Michigan License No. 27458