

**SURVEY &
REMONUMENTATION**

JAN 23 2001 LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

Clare County Remonumentation

For Corners in
Clare

(County)

Located In:

Corner Code#:

- | | | |
|---|----------------------------|------------|
| 1. Public Land Survey | T. <u>17N</u> R. <u>3W</u> | <u>F-7</u> |
| | T. _____ R. _____ | _____ |
| | T. _____ R. _____ | _____ |
| 2. Public Controlling in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 3. Miscellaneous Property in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 4. Lot No. _____, Recorded Plat | | |
| 5. Private Claims | | |

20000009293
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 11-14-2000 At 11:04 am.
LAND CORNER 9.00
OR Liber 2 Page 219 - 219

Instrument Liber Page
20000009293 OR 2 219

#424-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 15, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

Burt, 1850
Hemlock 20" East 12 LINKS
B. Ash 16" N74°W, 35 LINKS

LCRC #818-96 Robison, 1996
Fd 5/8" rod, 4 witnesses

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman Paul B. Latham
Date 8-23-00

C.S.R., Bk #1. Pg. 16, Johnson 1903
Stake & stones center of road
E-7, F-7 - 2626.14
F-7, G-7 - 2626.14

C.S.R. Bk #5. Pg. 16 Maple 6" N45°W, 07 LINKS

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 5/8" x 14" S.R. 1.05' North of line from E-7 to G-7 Measure 2622.52, - F-7 to G-7
Found witnesses per LCRC #818-96 Measure 2628.12, - F-7 to E-7
Fence line North & South. Searched for C.S.R. monument at found corner and at S.P.M. position and nothing found. Accepted found iron as best available evidence of position of corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

Set 5/8" x 36" re-rod with Clare County Remon Cap marked P. S #27458.

Witnesses:

N80°E, 101.93' - Found N & T South side of 12" Ash (OBT)
N15°E, 28.56' - Found N & T East side of 14" Ash
South 40.44' - Found N & T West side of P.P.
S50°E, 47.15' - N & T Northeast side of 4" x 8" x 3" x 3" Ash



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 11-13-2000