

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CLARE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>3W</u>	H-5
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED  
# 168-96  
96 NOV 16 PM 4:17  
REGISTER OF DEEDS  
CLARE COUNTY  
DORRIS M. BAKER  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARK R. ROBISON, in a field survey on AUGUST, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2			1
3												
4	7		8		9		10		11			12
5												
6	18		17		16		15		14			13
7												
8	19		20		21		22		23			24
9												
10	30		29		28		27		26			25
11												
12	31		32		33		34		35			36
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1850 BURT  
WIT.-BEECH 10" CORNER
- UNDATED C.S.R. L.S, PG. 10  
WIT.-W-PS 30" S35°W 64 LKS.  
H-5 TO H-4, 39.91 1/2 LKS.  
H-5 TO H-3, 79.67 CHS.
- 4-20-83 LAPHAM, L.C.R.C. #429  
WIT.-NAIL  
SOUTH, 27.95' - FENCE CORNER.  
S30°W, 35.10' - FENCE POST.  
NORTH, 38.25' - FENCE CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NAIL AND TAG AT RECORDED CORNER. FOUND 1/4"x2"x24" BAR, 3.60 FEET NORTH OF RECORDED CORNER. IRON BAR WAS 3 FEET BELOW SURFACE OF ASPHALT PVM'T. ACCEPTED BAR AS POSITION OF 1/4 CORNER. MEAS. WEST 2635.5 TO G-5  
MEAS. EAST 2637.2 TO I-5

See dossier for detailed report.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8"x36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MONUMENT BOX 2 1/2 FEET NORTH OF CENTER-LINE OF ASPHALT PVM'T. ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

- WITNESSES:
- SOUTH, 31.55' - NAIL & TAG IN CORNER FENCE POST.
  - NORTH, 34.65' - NAIL & TAG IN CORNER FENCE POST.
  - S38°W, 38.00' - NAIL & TAG IN FENCE POST.
  - N54°E, 61.15' - NAIL & TAG IN 8" ELM (CLUMP).

**APPROVED LAND CORNER**  
P.A. 345 of 1990  
Clare County  
Chairman Donald L. Lapham  
Date 11-07-96

Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458



Date 11-07-96