

RECEIVED  
 E 17 17  
 #182-96  
 96 DEC 23 AM 11:59

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CLARE</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>17N</u> R <u>3W</u>	<u>I-5</u>	
	T ___ R ___	___	___
	T ___ R ___	___	___
	T ___ R ___	___	___
2. Property Controlling in Section	S ___ T ___ R ___	___	___
	S ___ T ___ R ___	___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___	___
	S ___ T ___ R ___	___	___

REGISTER OF DEEDS  
 CLARE COUNTY  
 DONNA M. CARR

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, MARK R. ROBISON, in a field survey on AUGUST, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1850 BURT  
WIT.-Y. BIRCH 10" S70°E 14 LKS.  
Y. BIRCH 9" N15°W
  - 3-14-14 JOHNSON, C.S.R. L.2, PG. 32  
WIT.-S40°W 15 1/2 SCHOOL WELL 4"  
S34°W 125 CORNER OF SCHOOL HOUSE.
  - 8-10-05 JOHNSON, C.S.R., PG. 53  
WIT.-SCHOOL WELL S6°W 153 LKS.  
I-5 TO G-5 79.22'
  - 4-18-07 JOHNSON, C.S.R. L.4, PG. 100  
WIT.- I-7 TO I-5, 80.52'.
  - 8-23-07 JOHNSON, C.S.R. L.4, PG. 122  
WIT.-FLOWING WELL S6°W 1.5 CHS.
  - 6-29-08 JOHNSON, C.S.R., PG. 138  
WIT.-SCHOOL WELL 4" S6°W 153 LKS.  
COR. OF SCHOOLHOUSE S34°W 125 LKS.
  - UNDATED C.S.R. L.5, PG. 10  
WIT.-I-5 TO I-3 79.75'  
SCHOOL WELL 3" S4°W 153 LKS.

- UNDATED C.S.R. L.5, PG.11  
WIT.-I-5 TO K-5 80.3'  
SCHOOL WELL 3" S4°W 153 LKS.  
COR. OF SCHOOL HOUSE S34°W 125 LKS.
- UNDATED C.S.R. L.5, PG. 15  
WIT.-I-5 TO I-7 80.52'
- 4-20-83 LAPHAM, L.C.R.C. #479  
WIT.-FOUND NAIL & R.R. SPIKE.  
N70°E, 109.9' - S.W. COR. BLDG.  
N30°E, 79.70' - PROJECT MARKER.  
N30°W, 52.30' - STOP SIGN.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND R.R. SPIKE. EXCAVATED FOR ADDITIONAL EVIDENCE. FOUND 1/2" IRON LYING HORIZONTAL APPROXIMATELY 2 FEET NORTH AND ABOUT 1 1/2 FEET DEEP, JUST ABOVE OLD GRAVEL ROAD BED. DID NOT REMOVE IRON. ALL EVIDENCE OF THE SCHOOL HOUSE AND FLOWING WELL IS GONE. ACCEPTED R.R. SPIKE AT INTERSECTION OF CENTER-LINE, AS POSITION OF CORNER.  
 MEAS. 2637.2 WEST TO H-5 CRS DIM 2619.5 (SEARCHED BUT COULD NOT FIND ANY EVIDENCE OF CRC CORNER)  
 MEAS. 590' SOUTH TO SOUTH SIDE STREAM (GLO 561)  
 MEAS. 570' WEST TO WEST SIDE STREAM (GLO 436.92) OLD STREAM BED FULL IN WEST SIDE OF SWAMPY AREA, 435± WEST OF CORNER  
 MEAS. 1321' WEST TO REMNANTS OF FENCE TO NORTH  
 MEAS. 5272.7 WEST TO G-5 (CSR 5228.52)  
 MEAS. 5299.96 EAST TO K-5 (C.S.R. 5314.32)

APPROVED LAND CORNER  
 P.A. 345 of 1990  
 Clare County

See dossier for detailed report.

Chairman Paul S. Lapham  
 Date 11-14-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8"x36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MONUMENT BOX.  
 ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

- WITNESSES:
- S35°W, 115.10' - NAIL & TAG IN POWER POLE.
  - S31°E, 113.56' - NAIL & TAG IN 12" ASH.
  - N40°W, 63.78' - NAIL & TAG IN 10" ELM.
  - N22°E, 79.86' - CENTER OF PROJECT MARKER (OBT).
  - N70°E, 109.5' - S.W. COR. BLDG. (OBT).
  - N30°W, 52.80' - STOP SIGN (OBT).



Signed by Mark R. Robison  
 Surveyor's Michigan License No. 27458

Date 12-20-96