

JAN 23 2001

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Clare County Remonumentation**

200000009296  
 Filed for Record in  
 CLARE COUNTY MICHIGAN  
 CAROL MCAULAY  
 On 11-14-2000 At 11:04 am.  
 LAND CORNER 9.00  
 OR Liber 2 Page 222 - 222

For Corners in  
Clare

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 17N R. 3W I-7  
 T. \_\_\_\_\_ R. \_\_\_\_\_  
 T. \_\_\_\_\_ R. \_\_\_\_\_
- 2. Public Controlling S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
 in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
- 3. Miscellaneous S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
 Property in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Instrument Liber Page  
 200000009296 OR 2 222

# 427-00

**Register of Deeds Stamp & File Number**

I, Mark R. Robison, in a field survey on March 17, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- |  |  |  |
|--|--|--|
| G.L.O.<br>Burt, 1850<br>Hemlock 7" S71°E, 21 LINKS<br>Hemlock 7" N71°W, 11 LINKS   | C.S.R. Johnson, 1907 Bk. 4 Pg. 100<br>Birch 8" N25°W, 112 LINKS                            | C.S.R. Circa, 1900, no surveyor<br>Bk. 5. Pg. 15 Birch<br>Same as C.S.R. Bk. 2 Pg. 32  |
| C.S.R. Johnson, 1903 Bk 1 Pg. 17<br>& Bk. 4. Pg. 18<br>Stake drove through wagon wheel<br>thimble witnessed by 2 plow points<br>50 LINKS South | C.S.R. Johnson, 1914, Bk. 2. Pg. 32<br>Wagon Scain for corner<br>Birch 8" N25°W, 112 LINKS | C.S.R. Bk. 5 Pg. 22, Circa, 1900<br>no surveyor. Measured I-7 to<br>G-7 - 79.57  |
|  | Moore, 1955, Bk. 3 Pg. 32<br>Middle 3-12" trees S40°E, 76.0<br>Tele Pole N32°E, 38.5       | Survey Lapham, 1975 L1. Pg 994<br>Fd angle iron, 3 witnesses<br>Lapham, LCRC #116-73 - #206-75<br>Fd angle iron, 3 witnesses |

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- |   |  |   |
|---|--|---|
| Found 1" x 30" Angle Iron<br>Excavated to 2' found nothing further. | Found witness from C.S.R.<br>Moore 1955 Bk. 3, Pg. 32<br>Tele. Pole N32°E, 38.5' | Found material and 2 witnesses per<br>LCRC #116-73 and material and 3<br>witnesses from LCRC #206-75 and<br>survey 1-994. Accepted found angle iron<br>as perpetuation of CSR corner. |
| Dist to G-7 measures 5251.18 matches CSR 5-22                       |  |   |

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
 Set 5/8" x 36" re-rod with Clare County Remon Cap marked P.S. #27458.

- Witnesses:  
 N30°E, 38.55' - N & T Tele Pole (Stub) (OBT)  
 South, 34.70' - N & T Corner Fence Post (OBT)  
 S40°W, 101.90' - N & T Power Pole (OBT)  
 N60°W, 64.18' - N & T Fence Post



**APPROVED LAND CORNER**  
 P.A. 345 of 1990  
 Clare County  
 Chairman Paul A. Spiker  
 Date 8-30-00

Signed by Mark Robison  
 Surveyor's Michigan License No. 27458

Date 11-13-2000