

**SURVEY &  
REMONUMENTATION**

JAN 23 2001

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Clare County Remonumentation**

SECTION

For Corners in  
Clare

(County)	Located In:	Corner Code#:
1. Public Land Survey	T. <u>17N</u> R. <u>3W</u>	<u>J-7</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

200000009297  
 Filed for Record in  
 CLARE COUNTY MICHIGAN  
 CAROL MCAULAY  
 On 11-14-2000 At 11:04 am.  
 LAND CORNER 9.00  
 OR Liber 2 Page 223 - 223

Instrument Liber Page  
 200000009297 OR 2 223

# 428-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 17, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.  
 Burt, 1850  
 Hemlock 10" S17°E, 14 LINKS  
 Cedar 12" N25°W, 14 LINKS

Surveys, 1973 Urbaniak, Not recorded  
 Found 3/4" Bar & 3 witnesses

C.S.R., Bk. 2, Pg. 32, Johnson 1914  
 Fence Post 8" S46°

LCRC, Lapham #116-73  
 Found 3/4" Bar & same 3 witnesses as 1973 survey

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 3/4" x 14" Sucker Rod and 2 witnesses from #116-73

Measured:

I-7 to J-7 2637.74'

J-7 to K-7 2636.10'

Accepted found rod as best available evidence of the accepted position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" re-rod with Clare County Remon Cap marked P.S. #27458.

Witnesses:

S79°W, 132.86' - N & T Corner Fence Post (R.R. Tie)

S76°E, 188.88' - N & T Corner Fence Post (R.R. Tie)

South 4' +- - Centerline of E-W Road (OBT)

South 71.55' - N & T in P.P. (OBT)

**APPROVED LAND CORNER**  
 P.A. 345 of 1990  
 Clare County

Chairman Paul S. Lapham  
 Date 8-30-00



Signed by Mark R. Robison

Date 11-13-2000

Surveyor's Michigan License No. 27458