

**SURVEY &
REMONUMENTATION**

JAN 14 1999

SECTION

Clare County Remonumentation

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

_____ Clare _____ (County)	Located in:	Corner Code #
1. Public Land Survey	T17N R03W	K-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED
#325-98
98 DEC 29 PM 3:05
REGISTER OF DEEDS
CLARE COUNTY
CAROL A. HEARLAY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Mark R Robison, in a field survey on August, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- K-5: 1850 BURT- HEMLOCK 16 N81E 23
BEECH 6 N40W 18
- 5-18-01 HARPER- STAKE UNDER STONE CSR 1-71
W. PINE STUMP 20 S37E 51 LINKS
MEAS K-5 TO M-5, 79.96 CH.
- 5-29-08 JOHNSON- COR. OF CHURCH N 461/2E, 103 (CSR 5-11; CSR 1-138; CSR 2-32)
K-3 TO K-5 81.16
K-5 TO I-5 80.30
- UNDATED CIRCA- 1900 K-5 TO M-5 80.30 CSR 5-13
- 10-31-89 ROBISON- FD SPIKE UNREC. SURVEY & NOTES.
N45E 70.83 S.W. COR CHURCH
S45W 40.05 POW. POLE
S45E 83.43 POW. POLE
S30W 60.23 POW. POLE
MEAS N 5368/0 TO K-3 & E

11-29-89 LAPHAM WIT. SAME AS 10-31-89 LCRC 586

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-5: FOUND 1/2" X 12" IRON IN ASPHALT PVMT. 1989 WITNESSES CHECK CLOSE. S.W. CORNER OF CHURCH IS 2.81 FEET LONGER THEN C.S.R. WITNESSES. SEARCHED WITH METAL DETECTOR FOR CORNER AT C.S.R., DISTANCE, BUT DID NOT FIND ANYTHING, AFTER ASPHALT WAS REMOVED FOR ROAD RE-CONSTRUCTION, EXCAVATED & DID NOT FIND CSR. MONUMENT, CHURCH IS CONCREETE BLOCK AND POSSIBLY HAS BEEN REBUILT SINCE 1908. ACCEPTED IRON AS CORNER, 1989 SURVEY MEAS. E 5292.60 (CSR 5299.8; & 5277.36') TO M-5. MEAS. WEST 5299.95 (CSR 5299.8') TO I-5. SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5: SET 5/8"X36" IRON WITH STD. CLARE CO REMON CUP MARKED PS 27458 IN MON BOX. ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSTION OF THE CORNER.

- N40E 70.83 S.W. COR CHURCH (OBT)
- S45E 83.52 N & T IN P.P. (OBT)
- S36W 60.10 N & T IN P.P. (OBT)
- N36W 72.72 N & T IN 18" APPLE TREE



APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman Paul A. Lapham
Date 12-08-98

Signed by Mark R. Robison

Surveyor's Michigan License No. 27458

Date 12-28-98