

CLARE COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
E D I O / F
#178-96
96 DEC 23 AM 11:58

REGISTER OF DEEDS
CLARE COUNTY
DONNA M. CARR

For corners in

CLARE (County)	Located In:	Corner Code #
1. Public Land Survey	T 17N R 3W	K - 7
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on November, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6			5			4			3		2
3												
4	7			8			9			10		11
5												
6	18			17			16			15		14
7												
8	19			20			21			22		23
9												
10	30			29			28			27		26
11												
12	31			32			33			34		35
13												

A. Description of original monument and accessories and/or subsequent restoration:

1850 BURT
WIT.-HEMLOCK 11" S41W 24
HEMLOCK 11" N26E 14

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND OLD 2" X 14" PIPE IN CENTER OF T-ROAD NORTH. REMOVED AND DID NOT FIND FURTHER EVIDENCE. THIS POSITION IS NOT SUPPORTED BY G.L.O. DIMENSIONS, HOWEVER, IT IS SUPPORTED BY LOCAL LINES OF OCCUPATION AND THE POSITION OF THE ROAD TO THE NORTH. MEAS. EAST 5401.88 TO M-7 (GLO 5280). MEAS. WEST 5274.10 TO I-7 (GLO 5331.48).

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman Paul D. Leph
Date 11-14-96

SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7: CORNER COMMON TO SECTIONS 13, 14, 23 & 24
SET 5/8" X 36" REROD WITH 3" CLARE COUNTY MONUMENT CAP AT POSITION OF 2" PIPE. ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

WITNESSES:
N35E 65.94' N&T IN 14" ASH
N39W 39.36' N&T IN TEL. STUD POLE
S50W 63.04' N&T IN 12" CEDAR
S32E 53.72' N&T IN 10" TWIN CEDAR

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 12-20-96

