

CLARE COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
ELECTRICAL
#179-96
96 DEC 23 AM 11:59

REGISTER OF DEEDS
CLARE COUNTY
DONNA M. CARR

For corners in

CLARE (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>3W</u>	<u>K - 9</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1850 BURT CAPPED IRON
SEC CORNER IN STREAM 4 WITNESSES (THIS CORNER SET IN ERROR)
WIT.-ELM 11" N73W 45'
LYNN 16" S43W 48'
(NOTES--COMM. AT SEC. COR. N89DEG. 30MIN.E, 00.65
OVER STREAM)

1-4-17 C.S.R. (BK. 5, PG. 25) K-9 TO L-9 40.70

12-18-87 LAPHAM--L.C.R.C.#551

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

ESTABLISHED 25 - 26 SECTION LINE BY IRON FOUND AT 25, 26, 35, 36 SECTION CORNER (K-11) AND REMAINS OF OLD FENCE ON AN EXTENSION OF ROAD C/L. FENCE BEGINS 4900 FEET NORTH OF K-11. CORNER (K-9) ESTABLISHED N00DEG.44MIN.16SEC.E, 5269.15 FEET FROM K-11 AND S00DEG.14MIN.20SEC.E, 5269.89 FEET FROM IRON AT K-7. CORNER FALLS IN RIVER AS NOTED IN G.L.O. SURVEY. SET & MONUMENTED REFERENCE POINT 100.00 FEET SOUTH OF CORNER. 12-18-78 IRON IS IN ERROR AND WAS REMOVED.

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County
Chairman Paul D. Lapham
Date 11-14-96

SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9: CORNER COMMON TO SECTIONS 23, 24, 25 & 26 CORNER FALLS IN RIVER. SET 5/8" X 36" IRON WITH 3" CLARE COUNTY MONUMENT CAP AT REFERENCE POINT S00DEG.44MIN.16SEC.W, 100.00 FEET FROM CORNER. ACCEPTED AS FAITHFUL RE-ESTABLISHMENT OF ORIGINAL CORNER POSITION.

WITNESSES:
N09E 18.33' N&T IN 24" MAPLE
S11E 78.55' N&T IN TWIN 30" & 36" R. OAK
N36W 29.22' N&T IN 8" MAPLE
S40W 28.73' N&T IN 10" ELM

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 12-20-96

