

RECEIVED  
 E [initials]  
 #175-96  
 96 DEC 23 AM 11:58

CLARE COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS  
 CLARE COUNTY  
 DONNA M. CARR

For corners in

CLARE  
 (County)

Located in:

Corner Code #

1. Public Land Survey

T 17N R 3W L - 7

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, MARK R. ROBISON, in a field survey on November, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 1850 BURT  
 WIT.-MAPLE 13" S60E 15  
 W PINE 30" N48E ?  
 C.S.R. RECORDS NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 SET AN S.P.M. 2700.99' BOTH WAYS. CORNER FALLS 3' SOUTH OF CENTER LINE OF GRAVEL ROAD ON LINE OF OCCUPATION TO SOUTH, I.e. FIELD LINE AND POSSIBLE OLD FENCE REMOVED.

APPROVED LAND CORNER  
 P.A. 345 of 1990  
 Clare County  
 Chairman Paul D. Lyle  
 Date 11-14-96

SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7: 1/4 CORNER COMMON TO SECTIONS 13 & 24  
 SET 5/8" X 36" REROD WITH 3" CLARE COUNTY MONUMENT CAP.  
 ACCEPTED AS BEST AVAILABLE EVIDENCE OF ACCEPTED POSITION OF CORNER.

WITNESSES:  
 S12W 27.48 N&T IN P.P.  
 S39W 61.40 N&T IN 8" MAPLE  
 N47W 48.40 N&T IN 6" ELM  
 N28E 57.68 N&T IN 12" ELM



Signed by Mark R. Robison  
 Surveyor's Michigan License No. 27458

Date 12-20-96