

CLARE COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
EX 111
#177-96
96 DEC 23 AM 11:58
REGISTER OF DEEDS
CLARE COUNTY
DONNA M. CARR

For corners in

<u>CLARE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>3W</u>	<u>M - 7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	A
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, MARK R. ROBISON, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 HODGSON POST IN SWAMP WIT.-SPRUCE 8" S63W 21 B. ASH 10" N73W 37	12-6-94 MEYERS-UNRECORDED SURVEY SET 1/2" CAPPED REROD WIT.-S50E 71.07 N&T IN F.P. N55W 55.70 8" MAPLE S30W 64.75 14" MAPLE S05E 35.05 8" ELM
C.S.R. RECORDS NONE	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" X 18" IRON IN C/L GRAVEL ROAD AND ON VERY OLD FENCES NORTH AND SOUTH. FOUND WITNESSES OF GLADWIN COUNTY SURVEY. REMOVED IRON AND FOUND NO FURTHER EVIDENCE OF THE CORNER. MEASURED WEST 5401.98 TO K-7 IN T-ROAD NORTH. MEASURED EAST 2650.18 (GLO 39.89) TO 1/4 CORNER & 5309.10 (GLO 79.89) TO SECTION CORNER.

APPROVED LAND CORNER
P.A. 945 of 1990
Clare County
Chairman Paul S. Lofgren
Date 11-14-96

SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7: CORNER COMMON TO SECTIONS 13 & 24 ON TWP. LINE
SET 5/8" X 36" REROD WITH 3" CLARE COUNTY MONUMENT CAP.
ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

WITNESSES:
N44W 55.64 N&T IN 7" MAPLE
S03E 35.00 N&T IN 10" ELM
N75E 165.60 N&T IN P.P.
S66W 72.42 N&T IN 20" MAPLE



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 12-20-96