

**SURVEY & REMONUMENTATION**

FEB 18 1994

**CLARE COUNTY REMONUMENTATION PROGRAM**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED  
 1993 DEC 20 PM 1:46

REGISTER OF DEEDS  
 CLARE COUNTY  
 DONNA M. CARR

COMMISSION  
 For corners in

CLARE (County)	Located In:	Corner Code #
1. Public Land Survey	T 17N R 4W	C-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, MARK R. ROBISON in a field survey on OCTOBER, 19 93  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
 1850 W.A. BURT, W. PINE 13" N 39°E, 12 LKS  
 HEMLOCK 15" S 85°W, 37 LKS  
 5-1-72 P. LAPHAM, LCRC 23-72  
 11-10-77 P. LAPHAM, LCRC 305-77  
 8-17-88 T. MUELLER, LCRC 568-89

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 FOUND CAPPED IRON  
 FOUND RECORDED WITNESSES:  
 SW, 49.36' - 12" OAK  
 ESE, 34.06' - POWER POLE  
 SE, 79.73' - 16" OAK  
 NW, 55.25' - 14" OAK  
 N 51°W, 33.35' - 3" YELLOW CONS. POWER MARKER

This Corner established in Clare County Remonumentation Program.  
 See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MON. BOX.  
 N 55°W, 55.25' - 18" OAK  
 S 80°E, 34.03' - POWER POLE  
 S 25°E, 79.75' - 18" OAK  
 S 50°W, 49.36' - 15" OAK



Signed by Mark R. Robison Date 11/24/93  
 Surveyor's Michigan License No. 27458