

SURVEY & REMONUMENTATION

FEB 18 1994

COMMISSION

CLARE COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
F O I O A O
1993 DEC 20 PM 1:45

REGISTER OF DEEDS
CLARE COUNTY
DONNA M. CARR

For corners in

CLARE (County)	Located In:	Corner Code #
1. Public Land Survey	T 17N R 4W	E-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, MARK R. ROBISON, in a field survey on OCTOBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1850 W.A. BURT, POST, ELM 10" S 31°W, 24 LKS
 B. ASH 6" N 81°E, 66 LKS
 11-30-02 HARPER, CSR 4-11
 10-26-03 A. JOHNSON, CSR 4-34
 6-4-45 A. JOHNSON, STAKE & STONES, BROKEN GLASS, CSR 3-11
 NW COR. BRIDGE N 71°E 57
 SW COR. BRIDGE S 77°W 55
 7-21-72 COURTWRIGHT, LCRC 40-72
 5-1-75 FLUHARTY, LCRC 260-77

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND "T" IRON IN CENTER OF ASPHALT PAVEMENT
 FOUND RECORDED WITNESSES:
 N 71°E, 37.62' - N.W. COR. BRIDGE (MEAS. 37± TO ABUTMENT)(MEAS. 41.7' TO PIPE RAIL)
 S 77°W, 36.3' - S.W. COR. BRIDGE (MEAS. S.E. 38± TO ABUTMENT)(MEAS. S.E. 40.0' TO PIPE RAIL)
 N 60°E, 28.85' - GUARD RAIL POST
 S 60°E, 27.27' - GUARD RAIL POST
 N 31°W, 64.75' - POWER POLE

This position is accepted as the best location for the corner according to long established use and acceptance as the section corner.

This Corner established in Clare County Remonumentation Program.
See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MON. BOX.
 N 31°W, 64.75' - POWER POLE
 N 60°E, 25.72' - NAIL IN GUARD RAIL POST
 S 60°E, 22.85' - NAIL IN GUARD RAIL POST
 S 40°W, 61.95' - 6" ELM



Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458

Date 11/24/93