

SURVEY & REMONUMENTATION

FEB 18 1994

CLARE COUNTY REMONUMENTATION PROGRAM

RECEIVED

1993 DEC 20 PM 1:45

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. CARR

CLARE (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>4W</u>	<u>G-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5							●						
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARK R. ROBISON, in a field survey on OCTOBER, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1850 W.A. BURT, POST, HEMLOCK 12" S 15°W, 28 LKS, HEMLOCK 10" N 14°E, 18 LKS
 6-4-45 JOHNSON, CSR 3-11
 10-2-72 LAPHAM, LCRC 56-72
 11-6-73 LAPHAM, LCRC 117-73

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 1/2" x 18" RE-ROD IN MON. BOX
 FOUND RECORDED WITNESSES:
 S 30°E, 46.7' - POST
 S 60°E, 47.6' - POST (BROKEN OFF)
 S 50°W, 44.5' (45.5') NEW POST
 N 50°E, 105.95' - 13" APPLE

This Corner established in Clare County Remonumentation Program.
 See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP.
 N 30°W, 85.60' - POWER POLE
 S 45°W, 81.10' - POWER POLE
 S 35°E, 46.95' - FENCE POST
 N 60°E, 69.80' - FENCE POST



Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458

Date 11/24/93