

FEB 18 1994

**CLARE COUNTY REMONUMENTATION PROGRAM**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED  
E 10 A 0  
1993 DEC 20 PM 1:46  
REGISTER OF DEEDS  
CLARE COUNTY  
DONNA M. CARR

For corners in

CLARE (County)	Located In:	Corner Code #
1. Public Land Survey	T 17N R 4W	G-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARK R. ROBISON, in a field survey on OCTOBER, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
1850 W.A. BURT POST MAPLE 12" N 11°E 10 LKS  
BEECH 10" S 06°W 33 LKS  
10-08-74 LAPHAM LCRC 168-74

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND 1/2" x 18" C.I. IN MON. BOX  
FOUND RECORDED WITNESSES:  
S 85°W, 31.34' - 3" ELM  
N 80°E, 27.45' - CORNER POST  
N 65°E, 32.17' - TOP OF 1st POST NORTH

This Corner established in Clare County Remonumentation Program.  
See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
SET 5/8" x 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MON. BOX.  
N 35°E, 49.10' - 3" ELM  
N 30°W, 62.74' - 10" ELM  
S 25°W, 71.32' - 6" ELM  
S 25°E, 62.13' - 5" ELM



Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 11/24/93