

FEB 18 1994

COMMISSION

CLARE COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
E O J O A T
1993 DEC 20 PM 1:46

REGISTER OF DEEDS
CLARE COUNTY
DONNA M. CARR

For corners in

CLARE
(County)

Located In:

Corner Code #

1. Public Land Survey

T 17N R 4W
T R
T R
T R

G-7

2. Property Controlling in Section

S T R
S T R

3. Miscellaneous Property in Sec.

S T R
S T R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

I, MARK R. ROBISON, in a field survey on OCTOBER, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
1850 W.A. BURT, POST,
11-30-02, HARPER, 4" CEDAR STAKE, HEMLOCK STUB 20", N 70°E, 24 LKS, CSR 4-11
4-15-03, JOHNSON, STAKE & BRICKS, CSR 1-15
10-19-71, URBANIAK, LCRC 11-71
5-1-72, LAPHAM, LCRC 25-72
8-18-79, SEDGEMAN, (132) 2-490

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 18" x 1/2" SQUARE BOAT SPIKE (1" DIA. HEAD)
FOUND RECORDED WITNESSES:
SE, 101.95' - N.W. COR. TWP. HALL
SW, 63.07' - POW. POLE
NE, 46.88' - FENCE POST

This Corner established in Clare County Remonumentation Program.
See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET 5/8" x 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP.
S 55°W, 64.41' - POWER POLE
S 50°E, 101.75' - N.W. COR. TWP. HALL
N 50°E, 49.68' - POWER POLE
N 50°W, 104.1' - N.E. COR. 1 CU.YD. STONE



Signed by

Mark R. Robison

Date

11/24/93

Surveyor's Michigan License No.

27458