

FEB 18 1994

COMMISSION CLARE COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
E 11 A D
1993 DEC 20 PM 1:46
REGISTER OF DEEDS
CLARE COUNTY
DONNA M. CARR

For corners in

CLARE (County)	Located In:	Corner Code #
1. Public Land Survey	T 17N R 4W	G-8
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on OCTOBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1850 W.A. BURT, POST, HEMLOCK 12" N 54°E, 23 LKS
BEECH 10" S 77°W, 10 LKS
11-30-02 HARPER, CROCKERY CSR 4-11
4-15-03 JOHNSON, STAKE CSR 1-15
5-1-72 LAPHAM, LCRC 25-72
6-4-90 GRAY, LCRC 608-90

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1/2" x 18" RE-ROD IN MON. BOX
FOUND RECORDED WITNESSES:
N 75°W, 111.76' - 18" MAPLE
SW, 87.63' - TOP @ PHONE BOX
SE, 79.75' - N.W. COR. CONC. PAD

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

This Corner established in Clare County Remonumentation Program.
See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP.
S 20°E, 79.75' - N.W. COR. CONC. PAD
7.2' x 9.5'
S 35°W, 82.00' - 5" TWIN ELM
N 70°W, 135.10' - 2nd 24" MAPLE
N 25°E, 76' 7-1/2" - 3" POPLAR



Signed by Mark R. Robison

Date 11/24/93

Surveyor's Michigan License No. 27458