

**SURVEY & REMONUMENTATION**

**JAN 23 2001**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**

**Filing Requirement of Act 74, Mich. P.A. 1970**

**Clare County Remonumentation**

200000010424  
Record in  
CLARE COUNTY MICHIGAN  
CAROL MCAULAY  
On 12-27-2000 At 02:34 pm.  
LAND CORNER 9.00  
OR Liber 2 Page 305 - 305

For Corners in  
Clare

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 17N R. 4W H-3  
T. \_\_\_\_\_ R. \_\_\_\_\_  
T. \_\_\_\_\_ R. \_\_\_\_\_
- 2. Public Controlling S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_ *Seg. 2*
- 3. Miscellaneous S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
Property in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

200000010424  
R/D/D

Instrument Liber Page  
200000010424 OR 2 305

#510-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on November 28, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

This is recorded to replace the LCRC recorded in Liber 2, Page 295, #500-00 which was indexed incorrectly as R3W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO, Burt, 1850

Set Post  
Hemlock 10" S29°E, 17 LINKS  
Hemlock 6" N6°W, 15 LINKS

1989, Robison, (132), .3-138  
Same witness as LCRC #538-86

Survey, MDOT, 1970, Unrecorded Survey

Set 3/4" x 12" lag screw in Mon. Box

Five witnesses

H-3 to I-3, 2646.16 feet

H-3 to G-3, 2660.33 feet

1989, Lapham, (132) 3-140  
Same witness as LCRC #538-86

**APPROVED LAND CORNER**

P.A. 345 of 1990

Clare County

Chairman *Paul S. Lapham*

Date 12-13-00

LCRC, Lapham, 1986, LCRC #538-86

Fd Mon. Box in C.L. Road

Three witnesses

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

Fd 3/4" x 12" Lag screw in Mon. Box in C.L. E-W road & on line with East R/W fence of U.S. 27 x-way. Verified two 1970 witnesses and all 1986 witnesses. Accepted lag screw as best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rered with Clare County Remon Cap marked P.S. #27458 in existing Mon. Box.

Witnesses:

S71°W, 44.23' - Chiseled x in S.E. Cor. Bridge wall (OBT)

N70°W, 44.23' - Chiseled x in N.E. Cor. Bridge wall (OBT)

N30°W, 21.32' - N & T in top of guard rail post (OBT)

S02°E, 15.15' - N & T in top of guard rail post (OBT)

Signed by *Mark R. Robison*  
Surveyor's Michigan License No. 27458



Date 12-22-2000

APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983