

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CLARE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>4W</u>	<u>H-7</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

RECORDED  
E 17  
#171-96  
96 NOV 14 PM 4:18  
REGISTER OF DEEDS  
CLARE COUNTY  
DONNA M. CARR  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARK R. ROBISON, in a field survey on AUGUST, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- |   |  |   |
|---|--|---|
| 1850 BURT<br>WIT.-SET 1/4 POST<br>TAMARAC 8" N88°E 10 LKS.<br>TAMARAC 6" S65°W 16 LKS.  | JULY 1963 MSHD US-10 X-WAY R/W PLANS<br>WIT.-MEAS. 2637.05' WEST TO G-7.<br>MEAS. 2651.00' EAST TO I-7   | 9-17-81 LAPHAM, P.B.L. & ASSOC. FILES.<br>WIT.-H-7 TO G-7 MEAS. 2637.35'<br>H-7 TO I-7 MEAS. 2651.48'   |
| 4-15-03 JOHNSON C.S.R. L.1, PG.15<br>C.S.R. L.4, PG.16<br>WIT.-CEDAR STAKE<br>CEDAR STUMP 10" N30°W 12 LKS.<br>H-7 TO I-7 40.04 1/2 | 10 & 11-1963 LAPHAM PBL & ASSOC. FILES<br>WIT.-MEAS. 2638.13' WEST TO G-7<br>4-4-75 LAPHAM, P.B.L. & ASSOC. FILES<br>WIT.-MEAS. 2638.22' WEST TO G-7<br>9-20-78 LAPHAM<br>WIT.-FOUND MON. BOX.<br>SOUTH 76.73' 16" OAK<br>S25°W, 82.50' - 4" OAK.<br>S43°W, 73.70' - 14" BIRCH.<br>N45°W, 57.14' - POWER POLE. | 3-12-96 ROBISON, P.B.L. & ASSOC. FILES<br>WIT.-SET 1/2" CAPPED RE-ROD.<br>SOUTH. 38.08' - S.E. COR. HDW.<br>S70°E, 111.02' - 24" ASH.<br>N35°E, 127.80' - 36" MAPLE.<br>N50°W, 69.96' - 10" POPLAR. |
| UNDATED C.S.R. L.5, PG. 166<br>WIT.-CEDAR STUMP 10" N30°W 12 LKS.   |  |   |
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- FOUND 1/2"x18" RE-ROD AND 1996 WITNESSES. MEASURED 2637.17' WEST TO G-7. MEASURED 2651.48' EAST TO I-7. CORNER IS ON LINE BETWEEN SECTION CORNERS.

See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- SET 5/8"x36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MONUMENT BOX.  
ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.
- WITNESSES:  
SOUTH. 38.08' - S.E. CORNER HEADWALL (OBT).  
S70°E, 111.02' - NAIL & TAG IN 24" ASH (OBT).  
N35°E, 127.80' - NAIL & TAG IN 36" MAPLE (OBT).  
N50°W, 69.96' - NAIL & TAG IN 10" POPLAR (OBT).

**APPROVED LAND CORNER**  
P.A. 345 of 1990  
Clare County  
Chairman Paul D. Lapham  
Date 11-07-96

Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458



Date 10-1-96