

SURVEY & REMONUMENTATION

JAN 23 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in
Clare

200000009701
 Filed for Record in
 CLARE COUNTY MICHIGAN
 CAROL MCAULAY
 On 11-29-2000 At 10:31 am.
 LAND CORNER 9.00
 OR Liber 2 Page 231 - 231

Instrument Liber Page
 200000009701 OR 2 231

(County)	Located In:	Corner Code#:
1. Public Land Survey	T. <u>17N</u> R. <u>4W</u>	<u>L-13</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

436-00
 Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on May 9, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO, Hodgson, 1837 Beech 10" N23 1/2"E, 31 LINKS Pine 28" N66°W, 22 LINKS	Survey, Lapham, 1972, Private Files Same as LCRC #56-72
C.S.R, Unknown, Circa 1900 Bk. 5 Pg. 180 W. Pine stump 30" S14°W, 44 LINKS	Survey, Lapham, 1972, Private Files Same as LCRC #56-72
Lapham, 1972, LCRC #56-72 Set 1/2" iron, 3 witnesses	Survey, Fluharty, 1983, L2. Pg. 803 Same as LCRC #446-84
Fluharty, 1984, LCRC #446-84 Found 5/8" iron with cap, 3 witnesses 2 the same as LCRC #56-72	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

No GLO or CSR witnesses found. Found 1/2" iron in monument box at approximate mid point of K-13 to M-13. Witnesses from LCRC #56-72 and 446-84 were good. Accepted found iron as best available evidence of accepted position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" roerd with Clare County Remon Cap marked P.S. #27458 in Mon. Box.
 Witnesses:
 N54°W, 103.12' - N & T in 20" Maple
 S65°W, 66.20' - SE Corner of Telephone Box (OBT)
 N10°W, 29.64' - Nail in Power Pole (OBT)
 S5°E, 77.79' - Nail in Power Pole (OBT)



APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County
 Chairman *Paul Leph*
 Date 9-06-00

Signed by *Mark R. Robison*
 Surveyor's Michigan License No. 27458

Date 11-28-2000