

**SURVEY & REMONUMENTATION**

JAN 14 1999

**SECTION**

**CLARE County Remonumentation**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED  
 #310-98  
 98 NOV 24 AM 10:24  
 REGISTER OF DEEDS  
 CLARE COUNTY  
 CAROL A. McAULAY

For corners in

CLARE	Located in:	Corner Code #
(County)		
1. Public Land Survey	T19N R03W	B-13
	T18NR 03W	B-1 ✓
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Mark R Robison, in a field survey on July, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
		18		17		16		15		14		13	
8													
		19		20		21		22		23		24	
9													
		30		29		28		27		26		25	
11													
		31		32		33		34		35		36	
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

This is a single corner common to T19N, R03W, B-13 and T18N, R03W, B-1

**A. Description of original monument and accessories and/or subsequent restoration:**

- B-13: 1838 Nicholson**  
 Wit.-Y. Pine 10 for 1/4 Sec. Post  
 2-14-07 Johnson CSR 4-82 & 5-42  
 Wit.-Pine Stump 20 S51W 43  
 Pine Stump 20 N18W 37  
 M.S.H.D. R/W Plan 18-R-2, Pg. 41  
 Corner is 5.25' S of centerline. Corner monumented in 1997 paving project  
 2875.5 West to A-13  
 2650.5 East to C-13
- 8-17-78 Meyers unrecorded survey  
 M.S.H.D. Mon Box  
 Wit.-S25E 36.70 4" Pine  
 S60E 76.00 6" Pine  
 North 46.90 Hub & Tag  
 N05E 36.80 Tel. Riser
- 5-5-94 Robison unrecorded survey  
 M.S.H.D. Mon. Box  
 same as 8-17-78 survey
- 8-7-75 McClung unrecorded survey  
 Set S 1/4 from M.S.H.D.  
 Meas. 2880.64 West to Sec. Cor

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- B-13: Found 1/2" x 18" C.I. in monument box 5.5 ft. South of centerline. Found two 1978 witnesses. Measured West 2880.53 (GLO 2888.16) to A-13. Measured 2655.59 East to C-13.**  
 See dossier for detailed report.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- B-13: B-13: Corner common to Section 6, T18N, R3W (B-1) & Section 31, T19N, R3W (B-13). Set 5/8" x 36" rod with Clare County Remonumentation Cap marked P.S.#27458 in Monument Box. Accepted as best available evidence of accepted position of the corner.**  
 Witnesses:  
 S25E 36.70', nail & tag, 8" Pine (OBT)  
 S60E 76.00', nail & tag, 20" Pine (OBT)  
 S03W 49.20', nail & tag, 18" Twin R. Oak  
 N05E 46.25' Tele Riser



**APPROVED LAND CORNER**  
 P.A. 345 of 1990  
 Clare County  
 Chairman Paul S. Lyle  
 Date 9-08-98

Signed by Mark R. Robison  
 Surveyor's Michigan License No. 27458

Date 11-23-98