

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
CLARE
(County)

Located in:

Corner Code #

- | | | | | | |
|--------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey | T | <u>18N</u> | R | <u>3W</u> | <u>B-7</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECEIVED
 E 10 A D
 # 89-95
 95 OCT -3 PM 2:47

REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M CARR

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	MP
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARK R. ROBISON, in a field survey on JULY, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 CANNON, SUGAR 11 FOR 1/4 SEC COR
 BEECH 16 NORTH 23.

6-03 JOHNSON R.R. IRON CSR
 CEDAR POST 6" - N 50
 MEAS 39.66' TO C-7 & 46.835' TO A-7
 GLO 87.12' A-7 TO C-7

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AND DID NOT FIND CORNER MATERIAL. MEASURED 5708.83 FEET (CSR 5708.67) FROM A-7 TO C-7. SET CORNER 2617.63 FEET (S.P.M) FROM A-7 IN CENTER-LINE OF ROAD & CENTER OF 66 FOOT R/W FENCES. EXCAVATED TO THREE FEET, DID NOT FIND ANYTHING. NEW FENCE LINES RUN NORTH & SOUTH APPROXIMATELY 2 FEET WEST OF CORNER. A PRORATION OF THE MEASURED DISTANCE FROM C-7 TO A-7 AGAINST GLO WOULD PLACE B-7 2621.13 FEET WEST OF C-7. WE ACCEPTED THE CSR POSITION.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman Paul R. Lipp
 Date 9-26-95

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7. 18-19 1/4 SECTION CORNER
 SET 5/8"x36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP.
 ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE PERPETUATION OF THE C.S.R. CORNER.
 WITNESSES

- N02°W 33.53' @STONE FENCE POST
- N38°W 44.28' N&T IN COR FENCE POST
- S02°W 33.42' N&T IN COR F. POST
- S48°W 57.84' N&T IN 5TH FENCE POST WEST



Signed by Mark R. Robison

Date 10-03-95

Surveyor's Michigan License No. 27458