

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in CLARE
(County)

Located In:

Corner Code #

- | | | | | | |
|--------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey | T | <u>18N</u> | R | <u>3W</u> | <u>C-7</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Section | S | | T | R | |
| | S | | T | R | |

RECEIVED
 E 10 A D
 # 90-95
 95 OCT -3 PM 2:47
 REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. CARR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, MARK R. ROBISON, in a field survey on JULY, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1856 CANNON, POST
 HEMLOCK 17 N42°W 23
 HEMLOCK 13 S34°E 42
- 06-03 JOHNSON, RR IRON CSR
 P. STUMP 20 S47°E 50
 MEAS 39.66' TO B-7
 MEAS 46.835' B-7 TO A-7

SURVEY &
 RE-MONUMENTATION
 DEC 6 1995
 COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 2"x24" VERY OLD PIPE RUSTED IN TWO. DID NOT FIND R.R. IRON. CORNER FALLS IN INTERSECTION OF CENTERLINES OF GRAVEL ROADS.
 MEASURED WEST 5708.83 FEET TO A-7 (CSR 5708.67 & G.L.O. 5749.92)

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County
 Chairman Paul S. Toph
 Date 9-26-95

This Corner established in Clare County Remonumentation Program.
 See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-7, 17-18-19-20 SEC COR
 SET 5/8"x36" REROD WITH 3" CLARE COUNTY MONUMENT CAP.
 ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.
 S45°W 45.68' N&T IN COR. FENCE POST
 S45°E 46.13' N&T IN COR. FENCE POST
 N45°W 55.20' 3" PIPE 7' HIGH
 N75°E 102.90' N&T IN 10" ELM



Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458

Date 10-03-95