

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED  
 E 101 A 11  
 # 91-95  
 95 OCT -3 PM 2:48

REGISTER OF DEEDS  
 CLARE COUNTY  
 DONNA M. GARR

For corners in CLARE Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey	T	<u>18N</u>	R	<u>3W</u>	<u>D-7</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

**Register of Deeds Stamp & File Number**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, MARK R. ROBISON, in a field survey on JULY, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1856 CANNON, POST  
 W. PINE 36 N27 1/4°W 36  
 HEMLOCK 12 S10°W 14
- 10-76 LAPHAM, FD 1/2"x1 1/2" IRON BAR  
 (132) SURVEY  
 NORTH 28.37' FENCE COR  
 SOUTH 33.33' FENCE COR  
 N30°W 32.70' GATE POST
- 10-76 LAPHAM SAME AS ABOVE LCRC

SURVEY &  
 REMONUMENTATION  
 DEC 03 1995  
 COMMISSION

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- FOUND 3/4"x2 1/4"x1'1" IRON BAR. 2' NORTH OF C.
- 10-76 (132 SURVEY) WITNESSES ARE GONE (DESTROYED)  
 RECORDED EAST 2612.55' TO E-7  
 NOTE: VERIFY 2612.55'

**APPROVED LAND CORNER**  
 P.A. 345 of 1990  
 Clare County  
 Chairman Donald Taylor  
 Date 9-26-95

This Corner established in Clare County Remonumentation Program.  
 See dossier for detailed report.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- D-7, 17-20 1/4 SEC. COR
- SET 5/8"x36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP
- ACCEPTED AS BEST AVAILABLE EVIDENCE OF ACCEPTED POSITION OF THE CORNER
- N65°W 66.29' 6" ELM N&T
- SOUTH 72.52' POWER POLE N&T
- S10°W 34.25' F. POST N&T
- S18°E 39.68' F. POST N&T



Signed by Mark R. Robison Date 10-03-95  
 Surveyor's Michigan License No. 27458