

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
 E 10 10
 # 93-95
 95 OCT -3 PH 2:48

For corners in CLARE Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey	T	<u>18N</u>	R	<u>3W</u>	<u>F-7</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. CARR

SURVEY &

DEC 03 1995

COMMISSION
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, MARK R. ROBISON, in a field survey on JULY, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 CANNON - POST
 W. PINE 28 S33 1/2°W 31
 W. PINE 30 N12°E 20

03-78 LAPHAM SET 1/2" CAPPED REROD
 SOUTH 28.53' FENCE POST (GONE)
 S40°E 51.35' 4" APPLE TREE
 NORTH 31.34' FENCE POST (GONE)
 N35°E 40.75' 10" POPLAR

10-04 JOHNSON - NO COR. MATERIAL. CSR
 CEDAR POST 8 S2°W 41
 MEAS 39.41' (GLO 40.0') TO G-7
 MEAS 39.41' (GLO 40.0') TO E-7

09-78 LAPHAM SET 1/2" CAPPED REROD SINGLE GLO PROPORTIONAL MEASUREMENT LCRC
 WITNESSES SAME AS ABOVE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2"x18" RE-ROD & WITNESSES PER 132 SURVEY & LCRC.
 CORNER FALLS 3 FEET SOUTH OF Q GRAVEL ROAD IN LINE WITH FENCES NORTH & SOUTH.
 MEAS WEST 2618.39' (CSR 2601.06') TO E-7 & RECORDED EAST 2618.05' (CSR 2601.06') TO G-7.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman David A. Cople


Date 9-20-95

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7 16-21 1/4 SEC COR
 SET 5/8"x36" REROD WITH 3" CLARE COUNTY MONUMENT CAP.
 ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.
 S70°W 110.05 N&T IN 40" ASH (4 TRUNKS)
 SOUTH 30.9 N&T IN FENCE POST (OLD POST REMOVED)
 S40°E 51.35 N&T IN 14" APPLE (OBT)
 N35°E 41.00 N&T IN 10" POPLAR (OBT)



Signed by Mark R. Robison

Date 10-03-95

Surveyor's Michigan License No. 27458