

RECEIVED  
 E. J. L. A. D.  
 # 94-95  
 95 OCT -3 PM 2:48

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in CLARE Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 18N R 3W \_\_\_\_\_ G-7  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

REGISTER OF DEEDS  
 CLARE COUNTY  
 DONNA M. CARR

SURVEY &  
 RE-MONUMENTATION

DEC 6 1995

COMMISSION  
 Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, MARK R. ROBISON, in a field survey on JULY, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1856 CANNON, OLD COR. 03-78 LAPHAM - FD 1/2 SQUARE BAR (132) SURVEY  
 HEMLOCK 10 S55°W 29' N 53°W 61.48' GAS LINE MARKER  
 HEMLOCK 13 N34°E 62 1/2' S48°W 44.88' COR FENCE POST
  - 1903 STAKE 3". CENTER OF ROAD. MEAS 40.70' TO H-7 S59°E 77.70' 6" PINE  
 N42°E 41.30' COR FENCE POST
  - 09-04 & 10-11 JOHNSON - NO COR. MATERIAL 10-78 LAPHAM - SAME AS ABOVE LCRC  
 CORNER OF TOWNHALL S27 1/2°E 175 CSR 08-82 LAPHAM - SAME AS ABOVE (132) SURVEY  
 MEAS. 39.41' (GLO 40.0') TO F-7 AND  
 39.76' (GLO 39.41') TO H-7

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 FOUND 1/2"x1/2"x48" IRON BAR IN CENTER-LINE OF CROSS ROADS.  
 RECORDED 2618.05' (CSR 2601.06') WEST TO F-7 AND  
 2628.71' (CSR 2624.16') EAST TO H-7.  
 FOUND TOWNHALL PER C.S.R.

APPROVED LAND CORNER  
 P.A. 345 of 1990  
 Clare County  
 Chairman Donald L. Leph  
 Date 9-26-95

This Corner established in Clare County Remonumentation Program.  
 See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- G-7, 15-16-21-22 SEC. COR  
 SET 5/8"x36" RE ROD WITH 3" CLARE COUNTY MONUMENT CAP.  
 ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE PERPETUATION OF C.S.R. CORNERS.  
 S30°E 115.32' N.W. COR TWP. HALL (CSR WITNESS)  
 S45°W 77.16' N&T IN P.P.  
 N53°W 61.30' GAS-LINE MARKER  
 N30°E 55.80' N&T IN 10" CEDAR  
 S59°E 77.70' N&T IN 16" NORWAY PINE



Signed by Mark R. Robison Date 10-03-95  
 Surveyor's Michigan License No. 27458