

SURVEY & REMONUMENTATION

JAN 14 1999

SECTION

CLARE County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
314-98
98 DEC 29 PM 3:04

REGISTER OF DEEDS
CLARE COUNTY
CAROL A. McAULAY

For corners in

| | | |
|---------------------------------------|-------------------|---------------|
| <u>CLARE</u> (County) | Located in: | Corner Code # |
| 1. Public Land Survey | T18N R03W | H-5 |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Mark R Robison, in a field survey on October, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | |
|----|---|----|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L |
| 2 | | 6 | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | | 7 | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | | 18 | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | | 19 | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | | 30 | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | | 31 | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

H-5: 1856 Cannon
S89-30W 39.53, 1/4 Corner in Lake
39.81 over Lake Trigonometrically & set witness post Tamarac S57-1/2W 83

1911 Johnson, CSR 4-51
Tamarac 7 S57-1/2W 85
Tamarac 8 N84W 136 Gov't. Tree

1909 Johnson, CSR 5-159; Same as above

1996 McVean, LCRC #820; See detailed description on LCRC.
Corner in Lake not set. S.P. position is witnessed as follows:
S89 48 54 W, 100.00' 2" AC on Sec. line
N89 48 54 E 366.10 4" PAS. B. C. on R1W & Sec. line
N89 48 54 E 723.98 4" PAS. B. C. on R1W & Sec. line
N0 28 02 W 1138.58 4" PAS. B. C. on shore-line & NS 1/4 line

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-5: H-5 falls in Lake. Found D.N.R. witness monument 100 feet West of Corner and D.N.R. monument 366.10 feet East of Corner. (Both are on Section line). Set two more witnesses to corner in lake. Also witnessed the D.N.R. monument on the West shore of the lake as:
S30E, 18.16', N & T in P.P.
S87W, 29.04', N & T in 2" triple Cedar
S56E, 73.36', N & T in top center of end guard rail post

See dossier for detailed information

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5: Corner falls in lake. S.P.M. position is accepted as best available evidence of the correct position of the corner.
Section line bearing is S89°48'54" W.
S89°48'54" W, 100.00', 2" D.N.R. monument (OBT)
N89°48'54" W, 366.10', 4" D.N.R. monument (OBT)
S80°39'04" W, 91.17', Nail & Tag in P.P.
S43°38'57" W, 58.12', Nail & Tag in top center end guard rail post

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman Paul H. Lapp
Date 12-23-98

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458



Date 12-23-98