

RECEIVED
 #141-96
 96 NOV 14 PM 4:14

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. CARR

For corners in

<u>CLARE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>3W</u>	<u>1-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, MARK R. ROBISON, in a field survey on AUGUST, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1856 CANNON
WIT.-SET POST
BEECH 12" N24°W 15 LKS.
LYNN 7" S42 1/2°E 50 LKS.
- 7-3-03 JOHNSON, C.S.R. L1, PG. 21
WIT.-STAKE (ALL CORNERS FOUND).
1-2 TO 1-1 = 40.84
1-2 TO 1-3 = 40.39
- 7-5-03 JOHNSON, C.S.R. L4, PG. 23
WIT.-SAME AS 7-2-03

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND OLD FENCES E & W. MEAS. 5360.06' 1-1 TO 1-3. (MEASURING NORTH) STARTING AT 1-3, FOUND FENCES (E-W) AT 1325', 2649' AND 3991'. A SINGLE PROPORTIONATE DIVISION WOULD SET THE CORNERS AT 1330.93' (6' NORTH OF FENCES), 2661.86 (13' NORTH OF FENCE) AND 3983.53' (7 1/2 FEET SOUTH OF FENCE). ACCEPTANCE OF THE E-W 1/4 LINE FENCE AS THE BEST EVIDENCE OF THE 1/4 CORNER LOCATION, PLACES THE SOUTH 1/8 CORNER ON THE FENCES AND THE NORTH 1/8 CORNER 14' SOUTH OF THE FENCE. WE ACCEPTED THE 1/4 LINE FENCE AS THE BEST EVIDENCE OF THE LOCATION OF THE 1/4 CORNER. SET CORNER ON LINE BETWEEN BETWEEN 1-1 & 1-3, 2649.00 FEET NORTH OF 1-2. CORNER FALLS IN CENTER OF NEW GRAVEL ROAD IN 8' FILL SECTION.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8"x36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP.
 ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

- WITNESSES:
- N30°E, 109.08' - NAIL & TAG IN POWER POLE.
 - N39°W, 56.91' - NAIL & TAG IN 16" ASH.
 - N75°E, 64.02' - NAIL & TAG IN 14" ASH.
 - N80°E, 27.28' - NAIL & TAG IN FENCE POST.
 - N82°W, 34.86' - NAIL & TAG IN FENCE POST.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County
 Chairman Frank H. Lephors
 Date 11-07-96

Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458



Date 10-1-96