

RECEIVED
 E 11 11
 1142-96
 96 NOV 14 PM 4:14

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CLARE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>3W</u>	<u>1-3</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. CARR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, MARK R. ROBISON, in a field survey on AUGUST, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1856 CANNON
 WIT.-B. ASH 12" S47 1/2°E 27 LKS. UNDATED C.S.R. L.5, PG. 38
 B. ASH 14" N19°W 34 LKS. WIT.-STAKE 1-3 TO 1-1 = 81.13
- 7-5-03 JOHNSON, C.S.R. L.1, PG. 21 UNDATED C.S.R. L.5, PG. 46
 WIT.-STAKE (ALL CORNERS FD.) WIT.-STAKE 6'
 1-3 TO 1-2 = 40.39 PINE 36" N71°E 200
 ELM 12" S75 1/2°W 62
 1-3 TO 1-4 = 39.44
- 7-3-03 JOHNSON, C.S.R. L.4, PG. 23 UNDATED C.S.R. L.5, PG. 47
 WIT.-SAME AS 7-5-03 WIT.-SAME WIT. AS C.S.R. L.5, PG. 46
 1-3 TO 1-4 = 39.95
- 11-04-08 JOHNSON, C.S.R. L.4, PG. 150 UNDATED C.S.R. L.5, PG. 47
 WIT.-STAKE PINE 36" N71°E 200 LKS. WIT.-SAME WIT. AS C.S.R. L.5, PG. 46
 ELM 12" S75 1/2°W 63 LKS. 1-3 TO 1-4 = 39.95
 ALL GOV'T. CORNERS FOUND

6-21-76 LAPHAM, L.C.R.C. #240
 WIT.-SET 1/2" CAPPED RE-ROD.
 N30°E, 54.61' CEN. PROJECT MARKER.
 N45°W, 37.74' - FENCE COR.
 S80°E, 88.19' - 16" WILLOW.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON IN PYM'T. AT INTERSECTION OF ROADS. FOUND 1976 WITNESS TREE, WEST BRANCH HAS BEEN CUT OFF. MEAS. SOUTH 2622.6 FEET TO 1-4. MEAS. NORTH 2649 FEET TO 1-2. THERE ARE EIGHTH-LINE FENCES AT MID-POINT. BOTH NORTH AND SOUTH OF THE CORNER.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8"x36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP.
 ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

- WITNESSES:
- S74°E, 89.04' - NAIL & TAG IN EAST BRANCH OF TWIN 30" WILLOW (OBT).
 - S32°W, 76.12' - NAIL & TAG IN ELM.
 - N50°W, 39.19' - NAIL & TAG IN ELM.
 - N43°E, 75.23' - NAIL & TAG IN POWER POLE.

APPROVED LAND CORNER
 P.A. 345 of 1980
 Clare County

Chairman [Signature]
 Date 11-07-96

Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458



Date 10-1-96