

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CLARE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>3W</u>	<u>1-4</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED  
#143-96  
96 NOV 14 PM 4:14  
REGISTER OF DEEDS  
CLARE COUNTY  
DONNA M. CARR  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARK R. ROBISON, in a field survey on AUGUST, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10	●	11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 CANNON WIT.-CEDAR 14" S25°W 6 LKS. W. PINE 36" N3°E 75 LKS.	6-21-76 LAPHAM, L.C.R.C. #240 WIT.-SET 1/2" CAPPED RE-ROD. WEST, 33.55' - POWER POLE. N30°W, 57.18' - 10" CEDAR N60°E, 40.70' - 3" CEDAR.
UNDATED C.S.R. L.5, PG. 46 WIT.-I-4 TO I-3 = 39.44 I-4 TO I-5 = 40.30 1/2	
UNDATED C.S.R. L.5, PG. 47 WIT.-I-4 TO I-3 = 39.96 I-4 TO I-5 = 39.75 (SEE BOOK, MAY BE TYPO. ERROR)	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON IN PVM'T. FOUND 1976 WITNESSES MEASURED NORTH 2622.6' TO I-3. MEAS. SOUTH 2613.72' TO I-5. THERE ARE EIGHTH-LINE FENCES AT MID-POINTS BOTH NORTH AND SOUTH OF CORNER. FOUND THREE 6-21-76 WITNESSES. 10" CEDAR IS STUMP.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8"x36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP.  
ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

WITNESSES:  
S82°E, 33.55' - N&T IN POWER POLE (OBT).  
N54°E, 40.70' - NAIL & TAG IN 8" CEDAR (OBT).  
N33°W, 58.96' - NAIL & TAG IN 8" CEDAR.  
S50°E, 53.25' - NAIL & TAG IN 15" W. PINE.

APPROVED LAND CORNER  
P.A. 345 of 1980  
Clare County

Chairman [Signature]  
Date 11-07-96

Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458



Date 10-1-96