

RECEIVED  
 E 11  
 #140-96  
 96 NOV 14 PM 4:14

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS  
 CLARE COUNTY  
 DONNA M. CARR

For corners in

<u>CLARE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>3W</u>	<u>1-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, MARK R. ROBISON, in a field survey on AUGUST, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

- A. Description of original monument and accessories and/or subsequent restoration:
- 1856 CANNON 10-19-71 LAPHAM, L.C.R.C. #13  
 WIT.-CEDAR 20" S63°W 30 LKS. WIT.-SET CAPPED 1/2" RE-ROD.  
 TAMARAC 21" N47 1/2°E 35 LKS. 16' NORTH OF ROAD INTERSECTION  
 MEASURED FROM NORTH FROM E 1/4 CORNER  
 & DOUBLED OVER FENCES
  - 5-7-09 JOHNSON, C.S.R. L.4, PG. 159  
 WIT.-SAME WITNESSES AS G.L.O. N30°W, 91.0' - POWER POLE.  
 S70°W, 37.4' - FENCE COR.
  - NO DATE C.S.R. L.5, PG. 46  
 WIT.-SAME WITNESSES AS G.L.O. 6-21-76 LAPHAM, L.C.R.C. #240  
 I-5 TO I-4 = 40.30 1/2 WIT.-FOUND 1/2" IRON.  
 N30°E, 46.69' - POWER POLE.  
 S85°E, 32.74' - FENCE COR.
  - NO DATE C.S.R. L.5, PG.47  
 WIT.-I-5 TO I-4 = 39.75 N45°W, 44.27' - TELE. POLE.

10-24-82 MUELLER, (132) L.2, PG. 765  
 WIT.-FOUND 1/2" IN PVM'T AS RECORDED.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON IN INTERSECTION CENTER-LINES ASPHALT PVM'T IN 6' FILL AREA. MEAS. NORTH 2613.72' TO I-4 (FOUND 1/8 LINE FENCES AT MID POINT) MEAS. NORTH 2622.60' I-4 TO I-3 (FOUND 1/8 LINE FENCES AT MID POINT) MEAS. SOUTH 2692.38' TO I-6 (FOUND 1/8 LINE FENCES AT 1304') THE MEASUREMENTS TO THE SOUTH DO NOT VALIDATE I-6 MEAS. SOUTH 2589.16' TO I-7 (FOUND 1/8 LINE FENCES AT 1282') ACCEPTED FOUND 1/2" IRON AS CORNER.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


SET 5/8"x36' RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP.  
 ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

WITNESSES:  
 N43°E, 46.74' - NAIL & TAG IN POWER POLE (OBT).  
 S55°W, 77.32' - NAIL & TAG IN 5" CEDAR.  
 EAST, 97.56' - NAIL & TAG IN ELM.  
 N44°W, 46.48' - NAIL & TAG IN COR. FENCE POST.

APPROVED LAND CORNER  
 P.A. 345 of 1990  
 Clare County

Chairman Paul R. Lepore  
 Date 11-07-96

Signed by Mark R. Robison  
 Surveyor's Michigan License No. 27458



Date 10-1-96