

**SURVEY &
REMONUMENTATION**

JAN 23 2001

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

SECTION

For Corners in
Clare

(County)

Located In:

Corner Code#:

- | | | |
|---|----------------------------|------------|
| 1. Public Land Survey | T. <u>18N</u> R. <u>3W</u> | <u>I-6</u> |
| | T. _____ R. _____ | _____ |
| | T. _____ R. _____ | _____ |
| 2. Public Controlling
in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 3. Miscellaneous
Property in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

200000010177
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 12-15-2000 At 07:44 am.
LAND CORNER 9.00
OR Liber 2 Page 300 - 300

Instrument Liber Page
200000010177 OR 2 300

505-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on May 9, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO, Cannon, 1856 Existing Post
W. Pine 24" N73 1/2°E 32 LINKS
W. Pine 22" S76°W, 18 1/2 LINKS
I-6 to I-5 = 40.29 chains
I-6 to I-7 = 40.49 chains

C.S.R. Johnson, 1911, Kb. 2 Pg. 14 & Bk. 5 Pg. 51
I-6 to H-6 = 40.135 chains
I-7 to I-6 = 40.17 chains

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

C.S.R. Johnson, 1907, Bk 4. Pg. 125
I-6 to J-6 = 40.265 chains
I-6 to K-6 = 80.54 chains

Lapham, 1971. LCRC #13-71
4 witnesses

Chairman *Paulis Lopez*
Date 12-13-00

Survey, Urbaniak, 1971 not recorded
Same as LCRC #13-71
I-6 to I-5 = 2633.5
Set from found center 1907 CSR and E1/4 corner of
Section 14. This location is very near single proportionate measure
position between I-5 and I-7, per G.L.O. notes.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

No GLO or CSR evidence of corner found. 1971 corner not found but 1 witness in place. Reset corner from 1971 survey (on line between I-5 and I-7 at record distance (2633.5') from I-5, found witness matches re-established corner). Accepted re-established iron as best available evidence of re-established CSR position of corner. Position is 9 feet North of centerline road to East and fits G.L.O. proration.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rered with Clare County Remon Cap marked P.S. #27458
Witnesses:
S06°E, 106.29' - N & T in Utility Pole (OBT)
S38°E, 61.04' - N & T in Fence Post
S80°E, 128.94' - N & T in 11" Elm
N85°E, 72.66' - Top of west end of 12" CMP

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 12/14/2000