

SURVEY & RECORDS

DEC 6 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
E 107 AD
96-95
95 OCT -3 PM 2:48

REGISTER OF DEEDS
CLARE COUNTY
DONNA M. CARR

| For corners in | Located in: | Corner Code # |
|--------------------------------------|-------------|---------------|
| CLARE (County) | | |
| 1. Public Land Survey | T 18N R 3W | I-7 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Section | S T R | |
| | S T R | |

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, MARK R. ROBISON, in a field survey on JULY, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1856 CANNON POST OLD COR., BEECH 9 S58°E 15', W. PINE 22 N61°E 29'
- 04-04 & 10-11 JOHNSON NO COR. MATERIAL MEAS EAST 40.36' (GLO 40.19') TO J-7 & WEST 39.76' (GLO 40.76') TO H-7 PINE 28 S43° E 48' (31.68') PINE 28 N34 1/2°E 63' (41.58')
- 06-79 LAPHAM (NO COR MATERIAL) (MEAS WEST 2619.55' TO H-7) (132) SURVEY S30°W 60.15' TELE POLE EAST 32.90' FENCE COR N30°W 84.60' WELL PIPE
- 09-79 LAPHAM FD READING, SET NAIL LCRC SAME WITNESSES AS ABOVE
- 09-88 LAPHAM SAME WITNESSES AS ABOVE (132) SURVEY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1"x16" PIPE 1 FOOT WEST OF N-S @ LINE. ALSO FOUND WITNESSES, WELL PIPE N30°W 84.60', F. POST EAST - 32.90', & TEL STUB POLE S30°W 60.50' (REC 60.15'). P.B.L. MEAS. WEST 2619.55' (CSR 2624.16' & GLO 2690.16') TO H-7.

APPROVED LAND CORNER

P.A. 345 of 1990

Clare County

Chairman Paul H. Keffe

Date 9-26-95

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-7, 14-15-22-23 SEC COR, SET MON BOX WITH 5/8"x36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP. ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER. S40°W 71.15' 8" W. PINE EAST 32.90' SPIKE IN FENCE POST (OLD) N15°E 81.37' 12" ELM N10°W 96.25' 10" SPRUCE N30°W 84.60' WELL PIPE (OLD) S30°W 60.50' TEL. STUD POLE (OLD)



Signed by Mark R. Robison

Date 10-03-95

Surveyor's Michigan License No. 27458