

DEC 1 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
E 10 40
97-95
95 OCT -3 PM 2:48

REGISTER OF DEEDS
CLARE COUNTY
DONNA M GARR

For corners in

CLARE
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 18N R 3W J-7
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, MARK R. ROBISON, in a field survey on JULY, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 CANNON - POST
BEECH 6 S75°W 14
BEECH 7 N40°E 6

04-04 JOHNSON - NO COR. MATERIAL.
MEAS W 40.36' (GLO 40.19') TO I-7 &
E 39.94' (GLO 40.48') TO K-7
P. STUMP 30 N 18
P. TREE 3 S38°W 41

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND FOUR WAY FENCE CORNER AND REMAINS OF PINE STUMP NORTH 12 FEET ±
FOUND 32" PINE RECENTLY BLOWN OVER AT S38°W 27'

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman Paul S. Topham

Date 9-26-95

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-7 14-23 1/4 CORNER
SET 5/8"x36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP.
ACCEPTED AS BEST AVAILABLE EVIDENCE OF PERPETUATION OF CSR CORNER.
N32°E 56.00' N&T 40" MAPLE
N70°E 32.90' N&T 10" ASH
N64°W 30.80' N&T 6" MAPLE (TWIN)
S38°W 27.06' N&T STUMP OF 32" PINE



Signed by Mark R. Robison

Date 10-03-95

Surveyor's Michigan License No. 27458