

MAR 24 2000

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For Corners in
Clare

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 18N R. 3W K-1
T. _____ R. _____
T. _____ R. _____
- 2. Public Controlling S. _____ T. _____ R. _____
in Section S. _____ T. _____ R. _____
- 3. Miscellaneous S. _____ T. _____ R. _____
Property in Section S. _____ T. _____ R. _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

199900010476
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 12-03-1999 At 02:36 pm.
LAND CORNER 9.00
OR Liber 2 Page 114 - 114

Instrument Liber Page
199900010476 OR 2 114

402-99

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on April 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1856 Cannon Int N. Bdy at Post of Old Cor 39
links East of Cor 35-36
Wit-Beech 18 S10W 16 & Sugar 10 S46E 37
Old Cor of Sec 1 & 2 Set Post

7-3-03 Johnson, CSR 4-23, 1-21
Stake Cor Cedar stake N60W 44
K-1 to J-1 39.94

3-23-72 Courtright LCRC #42
P.K. Nail in M-61Hwy
Wit-N45W 103.97 P.P.
S40W 111.14 P.P.

APPROVED LAND CORNER

P.A. 345 of 1990

Clare County

Chairman *[Signature]*

Date 12-08-98

1-01-80 Meyers (132) 2-538
Fd MSHD Mon. Box
Wit-S40E 89.40 10" Ash
N45W 103.97 P.P.
S40W 111.14 P.P.

7-30-03 Johnson, CSR 4-27, 5-37, 5-38
Stake old Cor

March 77 McGinnis LCRC #291
Fd P.K. Nail (for 35-36 Sec Cor)
Wit-NE 85.6 Face Conc Proj. Marker
S45E 125.4 Face Conc R/W Marker

Note: The MSHD 1933 corner
appears to be K-13, T19N, R3W.

1933 MSHD
1" Gas Pipe NE Cor Sec 2
Wit-N55-15E 38.30 2" Elm
N39-00W 40.90 3" Elm
S49-00E 52.60 6" Maple

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
See dossier for detailed report.

The 1972, 1977, & 1980 witnesses are to an existing monument at K-13, T19N, R03W, which appears to be a perpetuation of the 1933 MSHD corner. No evidence could be found of K-1. Therefore K-1 was set 25.74 feet (GLO distance) from the standard corner K-13 on the K-13/L-13 line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 5/8" x 36" rerod with Clare Co. Remon Cap marked P.S. #27458 in Mon. Box. Accepted as best available evidence position of the corner.
Witnesses:

S04°E, 57.60 Cen. of Horz. Control Monument #18103-1980
S41°W, 124.52 N & T in P.P.
N24°W, 169.02 N & T in P.P.
N13°E, 78.96 Top Cen. R/W Marker
West 25.74 Std. Cor K-13

Signed by *[Signature]*
Surveyor's Michigan License No. 27458

Date 12-3-99



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971