

DEC 01 1995

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CLARE
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 18N R 3W K-7
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

RECEIVED
E 101 A E
98-95
95 OCT -3 PM 2:48

REGISTER OF DEEDS
CLARE COUNTY
DONNA M CARR

Register of Deeds Stamp & File Number

I, MARK R. ROBISON, in a field survey on JULY, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 CANNON - OLD CORNER
WIT.- BEECH 10 N20°W 18 1/2
BEECH 7 S50°W 24 1/2

04-04 & 05-09 NO COR. MATERIAL
PINE 28, N67°E 74 CSR
MEASURE WEST 39.94' TO J-7
(GLO 40.48)

UNDATED PAUL B. LAPHAM & ASSOC
FILES - NO COR. MATERIAL
N30°W 34.10' POW. POLE
S70°W 62.9' 24" ASH
S05°W 39.0' TWIN ELMS

09-71 URBANIAK SAME AS PBL & A FILES.
(132) SURVEY

10-71 URBANIAK FD IRON (USED
PLATTED SEC. LINE) LCRC
SAME WITNESSES AS 09-71
(132) SURVEY

01-76 LAPHAM FD 1" PIPE (132)
SURVEY
N40°E 47.30' FENCE COR
N40°W 44.60' POW. POLE
S49°E 45.15' FENCE COR

08-77 URBANIAK SAME AS 01-76
(132) SURVEY

07-77 SEDGMAN FIELD NOTES FROM
PAUL B. LAPHAM FILES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-7 CORNER COMMON TO SECTIONS 13, 14, 23 AND 24

FOUND 3/4"x19" PIPE ON EDGE OF GRAVEL ROAD. FOUND FOUR OLD WITNESSES:

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman Paul B. Lapham
Date 9-26-95

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP.
ACCEPTED AS BEST AVAILABLE EVIDENCE OF ACCEPTED POSITION OF CORNER.
N25°W, 44.60' N&T POWER POLE (OBT)
N48°E 47.3' N&T FENCE COR (OBT)
S42°E 45.15' N&T FENCE COR (OBT)
S74°W 62.9' N&T 32" ELM (OBT PREVIOUSLY CALLED ASH)



Signed by Mark R. Robison

Date 10-03-95

Surveyor's Michigan License No. 27458