

MAR 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in  
Clare

(County)

Located In:

Corner Code#:

1. Public Land Survey T. 18N R. 3W L-1  
T. \_\_\_\_\_ R. \_\_\_\_\_  
T. \_\_\_\_\_ R. \_\_\_\_\_
2. Public Controlling S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
3. Miscellaneous S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
Property in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

199900010475  
Filed for Record in  
CLARE COUNTY MICHIGAN  
CAROL MCAULAY  
On 12-03-1999 At 02:36 pm.  
LAND CORNER 9.00  
OR Liber 2 Page 113 - 113

Instrument Liber Page  
199900010475 OR 2 113

#401-99

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on July 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

7-30-03 Johnson CSR 1-22, 4-27,  
5-37. Wit-Pine Stump 24" S18W 36  
Pine Stump 24" S31E 24  
L-1 to K-1 40.12 & L-1 to M-1 40.00

4-14-72 Courtright (132) 1-174  
P.K. Nail in M-61 Hwy  
Wit-S45E 105.98 P.P.  
South 73.32 Cor F. Post  
North 77.10 Cor F. Post  
Meas. 2651.35 to M-1

4-23-72 Courtright LCRC #42  
Wit-same (132) 1-174 EXC S45W  
105.98 P.P.

1933 MSHD Axie shaft N 1/4 Sec 1  
Wit-N02-30E 57.85 6" Elm  
N46-00W 63.90 2" Willow  
S01.00W 75.25 24" Stump

Note: The MSHD 1933 corner  
appears to be L-13, T19N, R3W

2-01-80 Meyers (132) 2-538 Fd P.K. Nail  
Wit-S45W 105.92 P.P.  
South 73.32 FE Cor  
North 77.10 FE Cor

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
See dossier for detailed report.

The 1933, 1972 & 1980 witnesses are to an existing monument that is L-13, T19N, R03W. Set Closing Corner L-1 at S.P.M. between K-1 & M-1 on the standard line L-13 to M-13. Corner L-1 falls 13.95' East of Standard Corner L-13. Meas. 2637.20 feet both ways.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rerod with Clare Co. Remon Cap marked P.S. #27458 in Mon. Box. Accepted as best available evidence of the accepted method of re-establishment of the corner.

Witnesses:

N08°W, 78.98 N & T in Cor. F. Post  
S13°W, 77.10 Top Cen. of R/W Marker  
S47°W, 114.38 N & T in P.P.  
S46°E, 92.54 N & T in 7" Ash  
West 13.95 Standard Corner L-13

APPROVED LAND CORNER  
P.A. 345 of 1990  
Clare County

Chairman *Paul J. [Signature]*

Date 12-08-98



Signed by *[Signature]*  
Surveyor's Michigan License No. 27458

Date 12-3-99