

DEC 01 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED  
E 10 A.D.  
# 99-95  
95 OCT -3 PM 2:49

REGISTER OF DEEDS  
CLARE COUNTY  
DONNA M. CARR

For corners in CLARE Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T 18NR 3W L-7  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
In Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, MARK R. ROBISON, in a field survey on JULY, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 1856 CANNON W. PINE 15 OLD 1/4 COR BEECH 14 S25°E 7
- 1909 ---- ROCK 24 COR. W. PINE 30 N22°E 27. W. PINE 18 S34°W 65 CSR
- 8-77 SEDGMAN - FIELD NOTES FROM PBL & A FILES
- 11-77 SEDGMAN SET 1/2" BAR FROM C.S.R. WITNESSES LCRC S34°W 42.9' BLAZED 18" PINE STUMP SOUTH 33.63' COR FENCE POST NORTH 32.93' COR FENCE POST N70°W 76.08' 6" OAK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2"x18" CAPPED IRON IN @ ABANDONED ROAD. FOUND ALL 1977 WITNESSES-DISTANCE SOUTH TO COR FENCE POST IS 34.15 FEET. ALL OTHER DISTANCES GOOD. FOUND STUMP OF OAK N70°W 76.08'. FENCE LINES NORTH & SOUTH FROM R/W FENCES.

APPROVED LAND CORNER  
P.A. 345 of 1990  
Clare County

Chairman Paul D. Teph  
Date 9-26-95

This Corner established in Clare County Remonumentation Program.  
See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-7 13-24 1/4 CORNER
- SET 5/8"x36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP.
- ACCEPTED AS BEST AVAILABLE EVIDENCE OF PERPETUATION OF C.S.R. CORNER.
- NORTH 32.93' N&T IN COR FENCE POST (OBT)
- N70°W 83.75' N&T IN 8" OAK
- SOUTH 34.15' N&T IN COR FENCE POST
- S63°E 65.51' N&T IN 30" MAPLE CLUMP
- S34°W 42.9' BLAZED 18" PINE STUMP (CSR)



Signed by Mark R. Robison Date 10-03-95

Surveyor's Michigan License No. 27458